

STATUTORY CHECKLIST [§58.35(a) activities]**for Categorical Exclusions and Environmental Assessments**

Note: Review of the items on this checklist is required for both Categorical Exclusions under Sec. 58.35(a) and projects requiring an Environmental Assessment under Sec. 58.36. If no compliance with any of the items is required, a Categorical Exclusion [58.35(a)] may become "exempt" under the provisions of Sec. 58.34 (a) (12). In such cases attach the completed Statutory Checklist to a written determination of the exemption. Projects requiring an Environmental Assessment under Sec. 58.36 cannot be determined to be exempt even if no compliance with Statutory Checklist items is found. Three items listed at Sec. 58.6 are applicable to all projects, including those determined to be exempt.

Project Name and Identification/Location: Selig Residence / #1011
35 Old Dam Road Fairfield, Connecticut

Area of Statutory or Regulatory Compliance	Not Applicable to This Project	Consultation Required*	Review Required*	Permits Required*	Determination of consistency Approvals, Permits Obtained*	Conditions and/or Mitigation Actions Required	Provide compliance documentation. Additional material may be attached.
Document Laws and authorities listed at 24 CFR Sec. 58.5							
1. Historic Properties [58.5(a)] [Section 106 of NHPA]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Consulted with State Historic Preservation Office (SHPO); Building built in 1928. SHPO determined the proposed work will have no adverse effect on the State's cultural resources. See attached SHPO letter dated 4/23/14.. SHPO recommends the federal agency provide concerned citizens the opportunity to comment on the proposed project.
2. Floodplain Management [58.5(b)] [EO 11988] [24 CFR 55]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Located in Flood Zone AE based on FEMA – Map Number 09001C0557G Revised July 8, 2013. See attached FIRMLET.
3. Wetland Protection [58.5 (b)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Anticipated impacts on wetlands minimal due to majority of activities limited to pre-storm building footprint. Consulted City of Fairfield Inland Wetlands. No mapped wetlands. See attached National Wetlands Mapper.
4. Coastal Zone Management [58.5(c)] [CGS 22a-100(b)]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Site is located within the Coastal Boundary as mapped by DEEP.
5. Water Quality – Aquifers [58.5(d)] [40 CFR 149] Clean Water Act 1977 Safe Drinking Water Act 1974	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Water Quality – N/A Project does not involving on-site water and sewer facilities nor is it in a sole source aquifer zone.
6. Endangered Species [58.5(e)] [16 U.S.C. 1531 et seq.] [CGS 26-310]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	NOT LOCATED AT WATERFRONT PROPERTIES WITH SANDY BEACHES - consult with Department of Interior Fish and Wildlife Database – See attached Department of Interior Fish and Wildlife report dated October 3, 2014.
7. Wild and Scenic Rivers [58.5 (f)] [16 U.S.C. 1271 et seq.]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Eightmile River is only designated wild & scenic river within program area running through Lyme, Salem and East Haddam, CT (rivers.gov; November 2012)
8. Air Quality [58.5(g)] [42 U.S.C. 7401 et seq.]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Clean Air Act, State Implementation Plan, HUD & EPA Regulations; in general, residential rehabilitation exempted w/no quantifiable increase in air pollution.

Area of Statutory or Regulatory Compliance	Not Applicable to This Project	Consultation Required*	Review Required*	Permits Required*	Determination of consistency Approvals, Permits Obtained*	Conditions and/or Mitigation Actions Required	Provide compliance documentation. Additional material may be attached.
9. Farmland Protection [58.5(h)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Agricultural land use conversion not anticipated. Adverse effects to agricultural resources are not anticipated; clearly defined urban areas. Location not considered protected farmland
Manmade Hazards: 10 A. Thermal Explosive [58.5(i)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	N/A for projects that do not add density
10 B. Noise [58.5(i)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Not applicable to project – restoration of structure substantially as it existed prior to Super Storm Sandy.
10 C. Airport Clear Zones [58.5 (i)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Not applicable - Two (2) FAA designated Commercial Service airports in program area: Tweed New Haven Regional and Groton-New London. This property is not located in an Airport Clear Zone. Property does not involve the purchase or sale of an existing property in an airport zone.
10 D. Toxic Sites [58.5 (i)(2)(i)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	The site has no known toxic history based on the attached Toxix Site Certification. The site: 1) is not listed on EPA Superfund National Priorities or CERCLA list. 2) is not located within 3,000ft of a toxic or solid waste landfill. 3) is not known to have an underground storage tank (which is not an underground storage fuel tank). 4) Is not known or suspected to be contaminated by radioactive chemicals or radioactive materials.
11. Environmental Justice [58.5(j)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Executive Order 12898 Program activities do not anticipate high & adverse human health and environmental effects on minority or low-income populations;
Document Laws and authorities listed at Sec. 58.6 and other potential environmental concerns							
12 A. Flood Insurance [58.6(a) & (b)]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Located in Zone AE – Map Number 09001C0557G Revised July 8, 2013. See attached FIRMLET Flood insurance required.
12 B. Coastal Barriers [58.6(c)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Property is not located in a Coastal Barrier Resource Zone. See attach map.
12 C. Airport Clear Zone Notification [58.6(d)]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Not applicable - Two (2) FAA designated Commercial Service airports in program area: Tweed New Haven Regional and Groton-New London. This property is not located in an Airport

Area of Statutory or Regulatory Compliance	Not Applicable to This Project	Consultation Required*	Review Required*	Permits Required*	Determination of consistency Approvals, Permits Obtained*	Conditions and/or Mitigation Actions Required	Provide compliance documentation. Additional material may be attached.
							Clear Zone. Property does not involve the purchase or sale of an existing property in an airport zone.
13. A Solid Waste Disposal [42 U.S.C. S3251 et seq.] and [42 U.S.C. 6901-6987 eq seq.]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Resource Conservation and Recovery Act and Solid Waste Disposal Act; Residential Exemption
13 B. Fish and Wildlife [U.S.C. 661-666c]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Fish and Wildlife Coordination Act: Program activities will not result in impounding, diverting, deepening, channelizing or modification of any stream or body of water; not a water control project.
13 C. Lead-Based Paint [24 CFR Part 35] and [40 CFR 745.80 Subpart E]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Lead paint found - See attached Limited Hazardous Materials Inspection Report from Fuss & O'Neill EnviroScience LLC dated April 2014, revised May 2014. Give tenant Notice about Lead. Compliance will include removal of lead-based paint hazards, notifications, and clearance examinations.
13 D. Asbestos	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Asbestos found – See attached Limited Hazardous Materials Inspection Report from Fuss & O'Neill EnviroScience LLC dated April 2014, revised May 2014. Compliance will include measures to minimize risk of exposure and when necessary abate any hazardous materials.
13 E. Radon [50.3 (i) 1]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Radon concentration less than 4 picocuries per liter of air. See attached Limited Hazardous Materials Inspection Report from Fuss & O'Neill EnviroScience LLC dated April 2014, revised May 2014. No action required.
13 F. Mold	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	No Mold Found - See attached Limited Hazardous Materials Inspection Report from Fuss & O'Neill EnviroScience LLC dated April, revised May 2014.
Other: State or Local 14 A. Flood Management Certification [CGS 25-68]	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Property inside Flood Zone AE on FEMA map 09001C0557G Revised July 8, 2013. Certification through the General Permit for CDBG-DR activities with DEEP required. See appendix B Certification form and required documents.
14 B. Structures, Dredging & Fill Act [CGS 22a-359 through 22a-363f]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Not applicable – this project is not waterward of the Coastal Jurisdiction Line.
14 C. Tidal Wetlands Act [CGS 22a-28 through 22a-35]	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Located in Title wetlands – see attached Zoning Location Survey.
14 D. Local inland wetlands/watercourses [CGS 22a-42]	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Not located in wetlands - see attached Zoning Location Survey.
14 E. Various Municipal Zoning Approvals	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Approvals required by Planning/Zoning Commission or ZBA. If any work outside original building footprint.

DETERMINATION:

- ☐ This project converts to Exempt, per §58.349a(12), because it does not require any mitigation for compliance with any listed statutes or authorities, nor requires any formal permit or license. Funds may be drawn down for this (now) EXEMPT project; OR
- ☒ This project cannot convert to Exempt because one or more statutes/authorities requires consultation or litigation. Complete consultation/mitigation requirements, publish NOI/RROF and obtain Authority to Use Grant Funds (HUD 7015.16) per §58.70 and 58.71 before drawing down funds; OR
- ☐ The unusual circumstances of this project may result in a significant environmental impact. This project requires preparation of an Environmental Assessment (EA). Prepare the EA according to 24 CFR Part 58 Subpart E.

Prepared by:

Name: Stephen Ball

10/3/14
Date

Responsible Entity or designee Signature:

Hermia Delaire, CDBG-DR Program Manager

Date

Print

Nissan Fairfield www.GetMillerized.com Huge Fairfield Nissan Inventory. Save Big On A New Nissan, Call Now.

Ad

YAHOO!
MAPS

35 Old Dam Rd, Fairfield, CT 06824-6386

Enter notes here

255



When using any driving directions or map, it is a good idea to double check and make sure the road still exists, watch out for construction, and follow all traffic safety precautions. This is only to be used as an aid in planning.





Powered by Vision Government Solutions, Inc.



MBLU : 234/ 190/ / /
Location: 35 OLD DAM ROAD
Owner Name: SELIG GABRIEL M & GAD J
Account Number: 01326

Parcel Value

Appraised Value	Assessed Value
821,200	574,840

Owner of Record

SELIG GABRIEL M & GAD J
 P O BOX 74
 SOUTHPORT, CT 06890-0079

Ownership History

Owner Name	Book/Page	Sale Date	Sale Price
SELIG GABRIEL M & GAD J	1799/13/4	3/6/1998	0
SELIG HOLDING PARTNERSHIP	1642/87-0	10/21/1996	0
REIDY PETER D	1600/27-1	6/7/1996	255,000
BIKE JOHN & MAUREEN	678/1181	1/27/1981	0

Land Use

Land Use Code	Land Use Description
1010	Single Fam MDL-01

Land Information

Size	Zone
0.11 AC	BD

Construction Detail

Building # 1	MODEL Residential	Stories: 2 Stories
STYLE Conventional	Exterior Wall 1 Wood Shingle	Exterior Wall 2 Wood on Sheath
Occupancy 1	Roof Cover Asphalt	Interior Wall 1 Plastered
Roof Structure: Gable/Hip	Interior Flr 2 Carpet	Heat Fuel Oil
Interior Flr 1 Hardwood	AC Type: None	Total Bedrooms: 04
Heat Type: Hot Water	Total Half Baths: 0	Total Rooms: 7
Total Bthrms: 3		

Building Information

Living Area: 1,880 square feet	Year Built: 1928	Building Value: 90,000
---------------------------------------	-------------------------	-------------------------------


Extra Features

Code	Description	Units
No Extra Building Features		

Outbuildings

Code	Description	Units
FGR1	GARAGE-AVE	324 S.F.
SHD1	SHED FRAME	180 S.F.

Building Sketch

**Subarea Summary**

Code	Description	Gross Area	Living Area
BAS	First Floor	940	940
FUS	Upper Story, Finished	940	940
UEP	Porch, Enclosed, Unfinished	30	0
WDK	Deck, Wood	200	0

35 OLD DAM ROAD**Location** 35 OLD DAM ROAD**Assessment** \$574,840**Mblu** 234/ 190/ / /**Appraisal** \$821,200**Acct#** 01326**PID** 19143**Owner** SELIG GABRIEL M & GAD J**Building Count** 1**Current Value**

Appraisal	
Valuation Year	Total
2013	\$821,200
Assessment	
Valuation Year	Total
2013	\$574,840

Owner of Record**Owner** SELIG GABRIEL M & GAD J**Sale Price** \$0**Co-Owner****Book & Page** 1799/13/4**Address** P O BOX 74**Sale Date** 03/06/1998

SOUTHPORT, CT 06890-0074

Ownership History

Ownership History			
Owner	Sale Price	Book & Page	Sale Date
SELIG HOLDING PARTNERSHIP	\$0	1642/87-0	10/21/1996
REIDY PETER D	\$255,000	1600/27-1	06/07/1996
BIKE JOHN & MAUREEN	\$0	678/1181	01/27/1981

Building Information**Building 1 : Section 1****Year Built:** 1928**Living Area:** 1880**Building Photo**


Building Attributes	
Field	Description
Style	Conventional
Stories:	2 Stories
Occupancy	1
Exterior Wall 1	Wood Shingle
Exterior Wall 2	Wood on Sheath
Roof Structure:	Gable/Hip

Roof Cover	Asphalt
Interior Wall 1	Plastered
Interior Wall 2	
Interior Flr 1	Hardwood
Interior Flr 2	Carpet
Heat Fuel	Oil
Heat Type:	Hot Water
AC Type:	None
Total Bedrooms:	4 Bedrooms
Total Bthrms:	3
Total Half Baths:	0
Total Xtra Flxtrs:	
Total Rooms:	7 Rooms
Bath Style:	Average
Kitchen Style:	Average



(<http://images.vgsi.com/photos/FairfieldCTPhotos//\02\02\60\71.jpg>)

Building Layout



Building Sub-Areas			
Code	Description	Gross Area	Living Area
BAS	First Floor	940	940
FUS	Upper Story, Finished	940	940
UEP	Porch, Enclosed, Unfinished	30	0
WDK	Deck, Wood	200	0
		2110	1880

Extra Features

Extra Features

No Data for Extra Features

Land

Land Use

Use Code	1010
Description	Single Fam MDL-01
Zone	BD
Alt Land Appr	No
Category	

Land Line Valuation

Size (Acres)	0.11
Depth	0

Outbuildings

Outbuildings				<u>Legend</u>
Code	Description	Sub Code	Sub Description	Size
FGR1	GARAGE-AVE			324 S.F.
SHD1	SHED FRAME			180 S.F.

Valuation History

Appraisal	
Valuation Year	Total
2012	\$821,200
2011	\$821,200
2010	\$821,200

Assessment	
Valuation Year	Total
2012	\$574,840
2011	\$574,840
2010	\$574,840

(c) 2013 Vision Government Solutions, Inc. All rights reserved.

William Somerville

From: Steve Zajac <szajac@hecole.com>
Sent: Tuesday, March 11, 2014 1:56 PM
To: William Somerville
Subject: RE: FFE Elevations For 8 Bay Edge Crt, 127 Mona Ter, 35 Old Dam Rd, & 175 James St. Fairfield

Bill,

Here is the elevation datum for the above referenced four sites we surveyed on Friday 7/7/14. We did not survey the 710 Rowland Road site. I had the understanding that we were not doing that site at this time. The crew probably wouldn't have had time to complete that site on Friday anyway. If it needs to be done, I will go & survey it ASAP. We'll have to get in contact with the home owner as we did before. Let me know.

Steve

35 Old Dam Road: FFE=7.65

2nd FFE=15.75

GFE (detached)= 4.90

Slab for Utilities=4.50

(Concrete slab is approx. 6' x 12' underneath the center of the house)

HAG=6.1

LAG=5.7

Deck LAG=6.3

Zone: AE Elev. 12

AE 13 - SEE ATTACHED FROM

STEVE ZAJAC

127 Mona Terrace: FFE=12.11

2nd FFE=19.5

GFE (detached)= 7.40

BFE (Utilities)=4.55

HAG=8.1

LAG=7.0

Deck LAG=7.5

Zone: AE Elev. 11

8 Bay Edge Court: FFE=11.64

2nd FFE=19.5

GFE (detached)= 9.30

BFE (Utilities)=4.40

HAG=9.2

LAG=8.6

Deck LAG=8.6

Zone: AE Elev. 11

175 James Street: FFE=9.35

2nd FFE=17.4

BFE (Utilities)=5.75

HAG=7.0

LAG=5.8

Deck LAG=5.8

Zone: AE Elev. 11

William Somerville

From: Steve Zajac <szajac@hecole.com>
Sent: Tuesday, March 11, 2014 2:27 PM
To: William Somerville
Subject: RE: Correction for the Zone of 35 Old Dam Road

Bill,
The correct flood zone for 35 Old Dam Road is AE 13, not AE 12 as I stated in my last e-mail.
Steve


FEMA 500 YEAR BFE: 16.25
FEMA ZONE AE: BFE=13.0
FFE=7.65
2ND FFE=15.75
GFE DETACHED=4.90
SLAB FOR UTILITIES=4.50
SLAB IS APPROX. 6' X 10' UNDER HOUSE
THE REST OF THE UNDERNEATH IS SAND.
HAG=6.1
LAG=5.7
DECK LAG=6.3



Department of Economic and
Community Development

Connecticut
still revolutionary

April 23, 2014



Hermia M. Delaire, Program Manager
CDBG-Sandy Disaster Recovery Program
Department of Housing
505 Hudson Street
Hartford, CT 06106

RE: Applicant #1011, 35 Old Dam Road, Fairfield, CT

Dear Ms. Delaire:

The State Historic Preservation Office (SHPO) has reviewed the above-named project. In the opinion of the SHPO, the proposed undertaking will have no effect upon the state's cultural resources.

This office appreciates the opportunity to have reviewed and commented upon the project.

We recommend that the responsible federal agency provide concerned citizens with the opportunity to review and comment upon the proposed undertaking in accordance with the National Historic Preservation Act of 1966.

For further information, please contact Julie Carmelich at (860) 256-2762.

Sincerely:

Daniel T. Forrest
State Historic Preservation Officer

State Historic Preservation Office

One Constitution Plaza | Hartford, CT 06103 | P: 860.256.2800 | Cultureandtourism.org

An Affirmative Action/Equal Opportunity Employer An Equal Opportunity Lender

STEPHEN BALL
294 White Deer Rocks Road
Woodbury, Connecticut 06798

April 7, 2014

Todd Levine
State Historic Preservation Officer
One Constitution Plaza, 2nd floor
Hartford, CT 06103

Re: Environmental Review –35 Old Dam Road, Fairfield, CT

Dear Mr. Levine:


An Environmental Review for renovations due to Super Storm Sandy at 35 Old Dam Road, Fairfield, CT is required for the use of CDBG-DR funding through the Connecticut Department of Housing. The review requires that State Historic Preservation Office determination regarding historic significance.

I have attached the State Historic Preservation Office review form, scope of proposed work, photographs, map, and assessor's cards.

We do not feel the property has any historic significance and are requesting a finding of "No Effect".

Should you have any questions or require any additional information, feel free to call me at (203) 509-7231.

Thanks,



Stephen Ball

Enc.



State Historic Preservation Office

One Constitution Plaza | Hartford, CT 06103 | 860.256.2800 | Cultureandtourism.org

PROJECT REVIEW COVER FORM

1. This information relates to a previously submitted project.

☐

You do not need to complete the rest of the form if you have been previously issued a SHPO Project Number. Please attach information to this form and submit.

SHPO Project Number _____
(Not all previously submitted projects will have project numbers)

Project Address 35 Old Dam Road Fairfield, CT
(Street Address and City or Town)

2. This is a new Project.

☒

If you have checked this box, it is necessary to complete ALL entries on this form.

Project Name Selig House Renovation

Project Location 35 Old Dam Road

City or Town Fairfield
Include street number, street name, and or Route Number. If no street address exists give closest intersection.

County Fairfield
In addition to the village or hamlet name (if appropriate), the municipality must be included here.

If the undertaking includes multiple addresses, please attach a list to this form.

Date of Construction (for existing structures) _____

PROJECT DESCRIPTION SUMMARY (include full description in attachment):

See attached Projected Scope and Magnitude of Cost prepared by
Quisenberry Arcari LLC dated February 19, 2014

TYPE OF REVIEW REQUESTED

a. Does this undertaking involve funding or permit approval from a State or Federal Agency?

☒ Yes ☐ No

Agency Name/Contact
CT Dept. of Housing

Type of Permit/Approval
CDBG-DR

State

Federal

☒☒☐☐☐☐

b. Have you consulted the SHPO and UCONN Dodd Center files to determine the presence or absence of previously identified cultural resources within or adjacent to the project area?

Yes

No

☐☒

If yes:

Was the project site wholly or partially located within an identified archeologically sensitive area?

☐☐

Does the project site involve or is it substantially contiguous to a property listed or recommended for listing in the CT State or National Registers of Historic Places?

☐☐

Does the project involve the rehabilitation, renovation, relocation, demolition or addition to any building or structure that is 50 years old or older?

☐☐



State Historic Preservation Office

One Constitution Plaza | Hartford, CT 06103 | 860.256.2800 | CultureandTourism.org

PROJECT REVIEW COVER FORM

The Historic Preservation Review Process in Connecticut Cultural Resource Review under the National Historic Preservation Act – Section 106 <http://www.achp.gov/106summary.html> involves providing technical guidance and professional advice on the potential impact of publicly funded, assisted, licensed or permitted projects on the state's historic, architectural and archaeological resources. This responsibility of the State Historic Preservation Office (SHPO) is discharged in two steps: (1) identification of significant historic, architectural and archaeological resources; and (2) advisory assistance to promote compatibility between new development and preservation of the state's cultural heritage.

Project review is conducted in two stages. First, the SHPO assesses affected properties to determine whether or not they are listed or eligible for listing in the Connecticut State or National Registers of Historic Places. If so, it is deemed "historic" and worthy of protection and the second stage of review is undertaken. The project is reviewed to evaluate its impact on the properties significant materials and character. Where adverse effects are identified, alternatives are explored to avoid, or reduce project impacts; where this is unsuccessful, mitigation measures are developed and formal agreement documents are prepared stipulating these measures. For more information and guidance, please see our website at: <http://www.cultureandtourism.org/cct/cwp/view.asp?a=3933&q=293820>

ALL PROJECTS SUBMITTED FOR REVIEW MUST INCLUDE THE FOLLOWING MATERIALS*:

☒ **PROJECT DESCRIPTION** Please attach a full description of the work that will be undertaken as a result of this project. Portions of environmental statements or project applications may be included. The project boundary of the project should be clearly defined**

☒ **PROJECT MAP** This should include the precise location of the project – preferably a clear color image showing the nearest streets or roadways as well as all portions of the project. Tax maps, Sanborn maps and USGS quadrangle maps are all acceptable, but Bing and Google Earth are also accepted if the information provided is clear and well labeled. The project boundary should be clearly defined on the map and affected legal parcels should be identified.

☒ **PHOTOGRAPHS** Clear, current images of the property should be submitted. Black and white photocopies will not be accepted. Include images of the areas where the proposed work will take place. May require: exterior elevations, detailed photos of elements to be repaired/replaced (windows, doors, porches, etc.) All photos should be clearly labeled.

For Existing Structures	Yes	N/A	Comments	
Property Card	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
For New Construction	Yes	N/A	Comments	
Project plans or limits of construction (if available)	<input type="checkbox"/>	<input type="checkbox"/>		
If project is located in a Historic District include renderings or elevation drawings of the proposed structure	<input type="checkbox"/>	<input type="checkbox"/>		
Soils Maps http://websoilsurvey.nrcs.usda.gov/app/HomePage.htm	<input type="checkbox"/>	<input type="checkbox"/>		
Historic Maps http://magic.lib.uconn.edu/	<input type="checkbox"/>	<input type="checkbox"/>		
For non-building-related projects (dams, culverts, bridge repair, etc)	Yes	N/S	Comments	
Property Card	<input type="checkbox"/>	<input type="checkbox"/>		
Soils Map (see above)	<input type="checkbox"/>	<input type="checkbox"/>		
Historic Maps (see above)	<input type="checkbox"/>	<input type="checkbox"/>		
STAFF REVIEW AREA	Above	Date	Below	Date
Indicate date of Review and Initials of Reviewer				

PROJECT CONTACT

Name Stephen Ball Title Consultant

Firm/Agency _____

Address 294 White Deer Rocks Road

City Woodbury State CT Zip 06798

Phone _____ Cell 203-509-7231 Fax _____

Email stephenjball@hotmail.com

*Note that the SHPO's ability to complete a timely project review depends largely on the quality of the materials submitted.

** Please be sure to include the project name and location on *each page* of your submission.



State Historic Preservation Office

One Constitution Plaza | Hartford, CT 06103 | 860.256.2800 | Cultureandtourism.org

PROJECT REVIEW COVER FORM

SHPO USE ONLY


Based on our review of the information provided to the State Historic Preservation Office, it is our opinion that:

- ☐ No historic properties will be affected by this project. No further review is requested.
- ☐ This project will cause no adverse effects to the following historic properties. No further review is requested:
- ☐ This project will cause no adverse effects to the following historic properties, conditional upon the stipulations included in the attached letter:
- ☐ Additional information is required to complete our review of this project. Please see the attached letter with our requests and recommendations.
- ☐ This project will adversely affect historic properties as it is currently designed or proposed. Please see the attached letter for further details and guidance.

Daniel T. Forrest
Deputy State Historic Preservation Officer

Date

JOINS PANEL 0419



MAP SCALE 1" = 500'



NFIP

FIRM

FLOOD INSURANCE RATE MAP
FAIRFIELD COUNTY,
CONNECTICUT
(ALL JURISDICTIONS)

PANEL 557 OF 626

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS

COMMUNITY
FAIRFIELD TOWNSHIP

NUMBER
156207

PANEL
557

SUFFIX
0

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.



MAP NUMBER
09001C0557G
MAP REVISED
JULY 8, 2013
Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov



U.S. Fish and Wildlife Service

National Wetlands Inventory

35 Old Dam Road

Oct 2, 2014

Wetlands

- Freshwater Emergent
- Freshwater Forested/Shrub
- Estuarine and Marine Deepwater
- Estuarine and Marine
- Freshwater Pond
- Lake
- Riverine
- Other



This map is for general reference only. The US Fish and Wildlife Service is not responsible for the accuracy or currentness of the base data shown on this map. All wetlands related data should be used in accordance with the layer metadata found on the Wetlands Mapper web site.

User Remarks:



United States Department of the Interior

FISH AND WILDLIFE SERVICE
New England Ecological Services Field Office
70 COMMERCIAL STREET, SUITE 300
CONCORD, NH 3301
PHONE: (603)223-2541 FAX: (603)223-0104
URL: www.fws.gov/newengland



Consultation Tracking Number: 05E1NE00-2015-SLI-0008

October 03, 2014

Project Name: Selig Residence

Subject: List of threatened and endangered species that may occur in your proposed project location, and/or may be affected by your proposed project.

To Whom It May Concern:

The enclosed species list identifies threatened, endangered, proposed and candidate species, as well as proposed and final designated critical habitat, that may occur within the boundary of your proposed project and/or may be affected by your proposed project. The species list fulfills the requirements of the U.S. Fish and Wildlife Service (Service) under section 7(c) of the Endangered Species Act (Act) of 1973, as amended (16 U.S.C. 1531 *et seq.*).

New information based on updated surveys, changes in the abundance and distribution of species, changed habitat conditions, or other factors could change this list. Please feel free to contact us if you need more current information or assistance regarding the potential impacts to federally proposed, listed, and candidate species and federally designated and proposed critical habitat. Please note that under 50 CFR 402.12(e) of the regulations implementing section 7 of the Act, the accuracy of this species list should be verified after 90 days. This verification can be completed formally or informally as desired. The Service recommends that verification be completed by visiting the ECOS-IPaC website at regular intervals during project planning and implementation for updates to species lists and information. An updated list may be requested through the ECOS-IPaC system by completing the same process used to receive the enclosed list.

The purpose of the Act is to provide a means whereby threatened and endangered species and the ecosystems upon which they depend may be conserved. Under sections 7(a)(1) and 7(a)(2) of the Act and its implementing regulations (50 CFR 402 *et seq.*), Federal agencies are required to utilize their authorities to carry out programs for the conservation of threatened and endangered species and to determine whether projects may affect threatened and endangered species and/or designated critical habitat.

A Biological Assessment is required for construction projects (or other undertakings having

similar physical impacts) that are major Federal actions significantly affecting the quality of the human environment as defined in the National Environmental Policy Act (42 U.S.C. 4332(2) (c)). For projects other than major construction activities, the Service suggests that a biological evaluation similar to a Biological Assessment be prepared to determine whether the project may affect listed or proposed species and/or designated or proposed critical habitat. Recommended contents of a Biological Assessment are described at 50 CFR 402.12.

If a Federal agency determines, based on the Biological Assessment or biological evaluation, that listed species and/or designated critical habitat may be affected by the proposed project, the agency is required to consult with the Service pursuant to 50 CFR 402. In addition, the Service recommends that candidate species, proposed species and proposed critical habitat be addressed within the consultation. More information on the regulations and procedures for section 7 consultation, including the role of permit or license applicants, can be found in the "Endangered Species Consultation Handbook" at:

<http://www.fws.gov/endangered/esa-library/pdf/TOC-GLOS.PDF>

Please be aware that bald and golden eagles are protected under the Bald and Golden Eagle Protection Act (16 U.S.C. 668 *et seq.*), and projects affecting these species may require development of an eagle conservation plan (http://www.fws.gov/windenergy/eagle_guidance.html). Additionally, wind energy projects should follow the wind energy guidelines (<http://www.fws.gov/windenergy/>) for minimizing impacts to migratory birds and bats.

Guidance for minimizing impacts to migratory birds for projects including communications towers (e.g., cellular, digital television, radio, and emergency broadcast) can be found at: <http://www.fws.gov/migratorybirds/CurrentBirdIssues/Hazards/towers/towers.htm>; <http://www.towerkill.com>; and <http://www.fws.gov/migratorybirds/CurrentBirdIssues/Hazards/towers/comtow.html>.

We appreciate your concern for threatened and endangered species. The Service encourages Federal agencies to include conservation of threatened and endangered species into their project planning to further the purposes of the Act. Please include the Consultation Tracking Number in the header of this letter with any request for consultation or correspondence about your project that you submit to our office.

Attachment



United States Department of Interior
Fish and Wildlife Service

Project name: Selig Residence

Official Species List

Provided by:

New England Ecological Services Field Office
70 COMMERCIAL STREET, SUITE 300
CONCORD, NH 3301
(603) 223-2541
<http://www.fws.gov/newengland>

Consultation Tracking Number: 05E1NE00-2015-SLI-0008

Project Type: Federal Grant / Loan Related


Project Description: Superstorm Sandy renovations



United States Department of Interior
Fish and Wildlife Service

Project name: Selig Residence

Project Location Map:



Project Coordinates: MULTIPOLYGON (((-73.2571836 41.1245734, -73.2565828 41.1240408, -73.2571622 41.1236367, -73.2577845 41.1241863, -73.2571836 41.1245734)))

Project Counties: Fairfield, CT



United States Department of Interior
Fish and Wildlife Service

Project name: Selig Residence

Endangered Species Act Species List

There are a total of 0 threatened or endangered species on your species list. Species on this list should be considered in an effects analysis for your project and could include species that exist in another geographic area. For example, certain fish may appear on the species list because a project could affect downstream species. Critical habitats listed under the **Has Critical Habitat** column may or may not lie within your project area. See the **Critical habitats within your project area** section further below for critical habitat that lies within your project. Please contact the designated FWS office if you have questions.

There are no listed species identified for the vicinity of your project.




United States Department of Interior
Fish and Wildlife Service

Project name: Selig Residence


Critical habitats that lie within your project area

There are no critical habitats within your project area.

JOINS PANEL 0419



MAP SCALE 1" = 500'



NATIONAL FLOOD INSURANCE PROGRAM

PANEL 0557G

FIRM

FLOOD INSURANCE RATE MAP
FAIRFIELD COUNTY,
CONNECTICUT
(ALL JURISDICTIONS)

PANEL 557 OF 626
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:
COMMUNITY
FAIRFIELD TOWNSHIP
LEGENDER
DATE
OFFICE

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.


MAP NUMBER
09001C0557G
MAP REVISED
JULY 8, 2013



Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps, check the FEMA Flood Map Store at www.msc.fema.gov

JOHN H. CHAFEE COASTAL BARRIER RESOURCES SYSTEM CONNECTICUT



Number of CBRs Units:	32
Number of System Units:	25
Number of Otherwise Protected Areas:	7
Total Acres:	9,245
Upland Acres:	1,130
Associated Aquatic Habitat Acres:	8,115
Shoreline Miles:	22

Boundaries of the John H. Chafee Coastal Barrier Resources System (CBRS) shown on this map were transferred from the official CBRs maps for this area and are depicted on this map (in red) for informational purposes only. The official CBRs maps are enacted by Congress via the Coastal Barrier Resources Act, as amended, and are maintained by the U.S. Fish and Wildlife Service. The official CBRs maps are available for download at http://www.fws.gov/habitatconservation/coastal_barrier.html

Limited Hazardous Materials Building Inspection Report

Storm Sandy Residential Rehabilitation Project
35 Old Dam Road
Fairfield, Connecticut

Quisenberry Arcari Architects, LLC
Farmington, Connecticut

April 2014
Revised May 2014



FUSS & O'NEILL

Fuss & O'Neill EnviroScience, LLC
50 Quarry Road
Farmington, CT 06031



FUSS & O'NEILL
EnviroScience, LLC

April 26, 2014
Revised May 29, 2014

Mr. Thomas Arcari
Principal
Quisenberry Arcari Architects LLC
318 Main Street
Farmington, CT 06032

**RE: Limited Hazardous Materials Building Inspection
Storm Sandy Residential Rehabilitation Project
35 Old Dam Road, Fairfield, Connecticut**
Fuss & O'Neill EnviroScience Project No. 20140277.A3E
Quisenberry Arcari Project No. 1346-06

Dear Mr. Arcari:

Enclosed is the report for the limited hazardous materials building inspection performed at 35 Old Dam Road in Fairfield, Connecticut.

The initial inspection was performed on April 8, 2014, by Fuss & O'Neill EnviroScience, LLC state-licensed inspectors and included an asbestos inspection, testing for lead-based paint, airborne radon assessment, mold assessment, and assessments for PCB-containing ballasts and mercury hazards. On May 7, 2014, EnviroScience performed a lead-based paint risk assessment.

The information summarized in this document is for the above-mentioned materials only. It does not include information on other hazardous materials that may exist in the property (such as underground storage tanks, PCB-containing building materials, etc.).


If you have any questions regarding the contents of this report, please do not hesitate to contact us at (203) 374-3748. Thank you for this opportunity to have served your environmental needs.

56 Quarry Road
Trumbull, CT
06611
T 203.374.3748
800.286.2469
F 203.374.4391

www.fando.com

Connecticut
Massachusetts
Rhode Island
South Carolina

Sincerely,


Kevin McCarthy
Project Manager

Enclosure



Robert L. May, Jr.
President
NEHA NRPP # 105366 RT

Table of Contents

Limited Hazardous Materials Building Inspection Report Quisenberry Arcari Architects LLC 35 Old Dam Road, Fairfield, Connecticut

1	Introduction	1
2	Asbestos Inspection.....	1
2.1	Methodology	2
2.2	Results	3
2.3	Discussion	4
2.4	Conclusions	4
3	Lead-Based Paint Testing	5
3.1	Methodology	5
3.2	XRF Testing Results	5
3.3	Dust Wipe Samples Results	6
3.4	Lead in Soil Sample Results	7
3.5	Lead in Drinking Water Sample Results.....	7
3.6	Conclusions	7
4	Assessment of PCB-Containing Fluorescent Ballasts	9
4.1	Methodology	9
4.2	Results	9
4.3	Conclusions	9
5	Assessment of Mercury-Containing Devices.....	10
5.1	Methodology	10
5.2	Results	10
5.3	Conclusions	10
6	Mold Visual Assessment	10
6.1	Observations.....	10
7	Airborne Radon Information, Sampling and Procedure	10
7.1	Radon Facts and Health Effects	10
7.2	Airborne Radon Sampling Methodology	11
7.3	Airborne Radon Quality Assurance Procedure	12
7.4	Airborne Radon Analytical Results	12
7.5	Conclusions	13

Table of Contents

Limited Hazardous Materials Building Inspection Report Quisenberry Arcari Architects LLC 35 Old Dam Road, Fairfield, Connecticut

Appendices

APPENDIX A	FUSS & O'NEILL ENVIROSCIENCE STATE LICENSES, CERTIFICATIONS AND ACCREDITATIONS
APPENDIX B	ASBESTOS SAMPLE RESULTS AND CHAIN OF CUSTODY FORMS
APPENDIX C	LEAD PAINT TESTING PROCEDURES AND EQUIPMENT
APPENDIX D	LEAD TESTING FIELD DATA SHEETS
APPENDIX E	LEAD IN DUST SAMPLE RESULTS AND CHAIN OF CUSTODY FORM
APPENDIX F	LEAD IN SOIL SAMPLE RESULTS AND CHAIN OF CUSTODY FORM
APPENDIX G	MOLD BULK SAMPLE RESULTS AND CHAIN OF CUSTODY FORM
APPENDIX H	AIRBORNE RADON GAS ASSESSMENT RESULTS AND CHAIN OF CUSTODY FORM

1 Introduction

On April 8, 2014, Fuss & O'Neill EnviroScience, LLC (EnviroScience) Environmental Technician, Mr. Robert Hobbins, performed a limited hazardous materials inspection of the residential structure at 35 Old Dam Road in Fairfield, Connecticut (the "Site"). Mr. Hobbins is a State of Connecticut-licensed Asbestos Consultant - Inspector and Certified Lead Paint Inspector. On May 7, 2014, EnviroScience Environmental Technician Mr. Ulkens Auguste performed a lead paint risk assessment within the residence. Mr. Auguste is a State of Connecticut-Certified Lead Paint Inspector/Risk Assessor. The residential structure was not occupied at the time and date of the inspection. Refer to *Appendix A* for EnviroScience certifications and licenses.

This inspection was performed in response to the planned renovations to damaged or impacted areas of the building caused by Superstorm Sandy as identified in the *Draft Residence Rehabilitation Letter* dated February 19, 2014, provided by Quisenberry Arcari Architects. The limited inspection consisted of the following:

- A inspection for asbestos-containing materials (ACM);
- Testing and risk assessment of painted surfaces for lead-based paint (LBP);
- An evaluation of fluorescent light fixtures for polychlorinated biphenyls (PCB)-containing light ballasts;
- An inventory of light tubes/lamps and devices for mercury;
- Airborne radon gas assessment; and
- A mold assessment.

2 Asbestos Inspection

A Property Owner must ensure that performance of a thorough inspection for ACM, prior to possible disturbance of suspect ACM during renovation or demolition, is conducted. This is a requirement of the United States (US) Environmental Protection Agency (EPA) National Emission Standards for Hazardous Air Pollutants (NESHAP) regulation located at Title 40 CFR Part 61, Subpart M.

This includes Friable, Non-Friable Category I, and Non-Friable Category II ACM.

- A Friable Material is defined as material that contains greater than one percent (>1%) asbestos, that when dry **can** be crumbled, pulverized, or reduced to powder by hand pressure.
- A Category I Non-Friable Material refers to material that contains greater than one percent (>1%) asbestos (e.g. packings, gaskets, resilient floor coverings, asphalt roofing products, etc.) that when dry **cannot** be crumbled, pulverized, or reduced to powder by hand pressure.
- A Category II Non-Friable Material refers to any non-friable material (excluding Category I materials) that contains greater than one percent (>1%) asbestos that when dry **cannot** be crumbled, pulverized, or reduced to powder by hand pressure.

During this inspection, suspect ACM were separated into three EPA categories. These categories are: thermal system insulation (TSI), surfacing ACM, and miscellaneous ACM. TSI includes all materials used to prevent heat loss or gain or water condensation on mechanical systems. Examples of TSI are pipe

insulation, boiler insulation, duct insulation, and mudded insulation on pipe fittings. Surfacing ACM includes all ACM that is sprayed, troweled, or otherwise applied to an existing surface. Surfacing ACM is commonly used for fireproofing, decorative, and acoustical applications. Miscellaneous materials include all ACM not listed in thermal or surfacing, such as linoleum, vinyl asbestos flooring, and ceiling tiles.

Samples are recommended to be collected in a manner sufficient to determine asbestos content and include homogenous building materials. The EPA NESHAP regulation does not specifically identify a minimum number of samples to be collected and analyzed, but recommends the use of sampling protocols included in EPA Title 40 CFR Part 763, Sub-Part E - Asbestos Containing Materials in Schools regulation.

2.1 Methodology

Samples of suspect ACM were collected in accordance with EPA recommendations and Asbestos Hazard Emergency Response Act (AHERA) protocols. The protocols included the following:

1. Surfacing Materials (SURF) (e.g., plaster, spray-on fireproofing, etc.) were collected in a randomly distributed manner representing each homogenous area based on the overall quantity represented by the sampling as follows:
 - a. Three samples collected from each homogenous area that is less than or equal to (\leq) 1,000 square feet.
 - b. Five samples collected from each homogenous area that is greater than ($>$) 1,000 square feet, but less than or equal to 5,000 square feet.
 - c. Seven samples collected from each homogenous area that is greater than ($>$) 5,000 square feet.
2. Thermal System Insulation (TSI) (e.g., pipe insulation, tank insulation, etc.) was collected in a randomly distributed manner representing each homogenous area. Three bulk samples were collected as representative of each homogeneous material type, and sent to laboratory for asbestos analysis. Also, a minimum of one sample of any patching material (less than 6 linear of square feet) applied to TSI was collected.
3. Miscellaneous Materials (MISC) (e.g. floor tile, gaskets, construction mastics, etc.) had a minimum of two samples collected as representative of each homogenous material type. Sampling was conducted in a manner sufficient to determine asbestos content of the homogenous material as determined by the Asbestos Inspector. If materials identified were of (significant) minimal quantity, only a single sample was collected.

The Asbestos Consultant – Inspector collected samples and prepared proper chain-of-custody for transmission of samples to an accredited asbestos analytical laboratory for analysis by Polarized Light Microscopy (PLM). The sampling locations, material type, quantity, sample identification, and asbestos content are identified by bulk sample analysis in Tables 1 and 2 of the “Results” section and Table 3 of the “Discussion” section. Any materials on the site not listed in the following tables should be considered suspect ACM until sample results indicate otherwise. Refer to *Appendix B* for PLM analytical results for suspect asbestos bulk samples.

2.2 Results

Utilizing the EPA protocol and criteria, the following materials were identified as ACM:

Table 1
Asbestos-Containing Materials

Location	Material Type	Asbestos Content	Estimated Quantity	Sample No.
Crawlspace	Internal Furnace Components (Gaskets, Rib Caulking, Roping, etc.)	Assumed	1 Furnace Unit	N/A
2 nd Floor Laundry Room	Bottom Layer Tan Sheet Flooring	10% Chrysotile; 10% Crocidolite	50 SF	0408BH19A
Exterior Roof	Chimney, Pipe & Vent Roof Flashings	Assumed	10 SF	N/A

Note: SF=Square Feet

Utilizing the EPA protocol and criteria, the following materials were determined to be **non-ACM**:

Table 2
Non-Asbestos Containing Materials

Location	Material Type	Sample No.
Main Floor	Textured Ceiling Paint	0408BH01A-G
Throughout Interior	Sheetrock & Taping/Joint Compound	0408BH02A-B, 03A-B, 04
Crawlspace	White Backing on Fiberglass Insulation	0408BH05A-B
Main Floor Foyer	Red Slate Floor Tile, Glue, and Grout	0408BH06A-B, 07A-B, 08A-B
Main Floor Master Bath	White/Green/Blue Sheet Flooring and Glue	0408BH09A-B, 10A-B
	Brown Cove Base & Glue	0408BH11A-B, 12A-B
Main Floor Foyer Bath	Self-Stick Floor Tile	0408BH13A-B
Main Floor Master Bath	Ceramic Tile, Grout, and Glue	0408BH14A-B, 15A-B, 16A-B
2 nd Floor Kitchen	Self-Stick Floor Tile	0408BH17A-B
2 nd Floor Laundry	Gray Top Layer, Self-Stick Floor Tile ¹	0408BH18A-B ¹
Building Exterior	Exterior Window Glazing Compound	0408BH20A-C
	Paper Vapor Barrier behind Exterior Siding	0408BH21A-B
Exterior Roof	Top & Bottom Layer Roof Shingles	0408BH22A-B, 23A-B

Location	Material Type	Sample No.
Exterior Annex Garage	Exterior Window Glazing Compounds	0408BH24A-C
	Concrete Block & Grout	0408BH25A-B, 26A-B

Note: 1. To be disposed as contaminated waste

2.3 Discussion

Sample analytical results are reported in percentages of asbestos and non-asbestos components. The EPA defines any material that contains more than one percent (1%) asbestos, utilizing PLM, as an ACM. Materials that are identified as “none detected” are specified as not containing asbestos. It is usually recommended that materials identified as containing less than one percent (<1%) friable asbestos be analyzed further using the EPA point count method.

2.4 Conclusions

Interior ACM identified in *Section 2.1 - Table 1* must be removed by a State of Connecticut-licensed Asbestos Abatement Contractor prior to building renovations that will disturb the materials. This is a State of Connecticut Department of Public Health (CTDPH) Standards for Asbestos Abatement requirement.

The non-friable roofing materials identified in *Section 2.1 - Table 1* have been de-regulated by the Connecticut Department of Public Health (CTDPH). The identified non-friable roofing materials may be removed by either a CTDPH-licensed Asbestos Abatement Contractor, or by a roofing contractor provided they adhere to all Occupational Safety and Health Administration (OSHA) training requirements and EPA NESHAP regulatory requirements. All asbestos waste must be properly sealed (leak/airtight containers) and disposed in a landfill approved to accept asbestos waste. A licensed Asbestos Abatement Contractor is only required should the ACM be made friable and become a regulated ACM (RACM) by work activities. If the roofing material becomes RACM, then all applicable CTDPH regulations shall apply.

Furnace Unit– The inaccessible furnace unit was not inspected at the time of the inspection and the associated internal materials are assumed to be ACM

Roof Flashing – The roof flashing was not inspected at the time of the inspection and is assumed to be asbestos containing.

Note that since this asbestos inspection was limited, we recommend conducting a supplemental inspection of hidden and inaccessible areas (behind walls/beneath fixed floors, exterior foundation, etc.) prior to demolition/renovation activities.

Note that since this asbestos inspection was limited, we recommend conducting a supplemental inspection of hidden and inaccessible areas (behind walls/beneath fixed floors, within mechanical equipment, exterior foundation, etc.) prior to demolition/renovation activities. Any suspect ACM encountered during

renovation activities that is not identified in this report as being non-ACM, should be assumed to be ACM unless sample results prove otherwise.

3 Lead-Based Paint Testing

EnviroScience conducted comprehensive testing for lead-based paint (LBP) within the residential Site structure. On April 7, 2014, Mr. Hobbins performed the testing. The purpose of the testing was for compliance with EPA's Renovation, Repair, and Painting Rule (RRP) located at Title 40 CFR, Parts 745.80 through 92, and the US Department of Housing and Urban Development (HUD) Lead-Safe Housing Rule (Title 24 CFR, Part 35, Subparts B-R). On May 7, 2014, Mr. August performed a risk assessment for the purpose of compliance with HUD Lead-Safe Housing Rule.

3.1 Methodology

A direct reading X-ray fluorescence (XRF) analyzer was used to perform the testing. The testing was conducted in accordance with the protocol outlined in the attached document: "Testing Procedures and Equipment" (refer to *Appendix C*).

For the purpose of this testing, various interior and exterior building components representing the initial painting history of the building, and any building-wide repainting by the owners/managers of these building components were tested. Individual repainting efforts are not discoverable in such a limited testing program. The purpose of this testing was to identify patterns and trends in the painting history of the buildings in order to determine if the EPA Toxicity Characteristic Leaching Procedure (TCLP) analysis is required for demolition debris prior to off-site disposal. Additionally, representative lead in dust wipe samples, lead in soil samples, and lead in drinking water samples were collected for the risk assessment portion of the project.

The structure is constructed of wood siding exterior with metal/wood window and door systems. The interior is composed of sheetrock with wood and concrete floors. There were no children under the age of six present within the residence at time and date of this inspection.

3.2 XRF Testing Results

The testing indicated consistent painting patterns and trends throughout the building interiors and exteriors. Of the building components tested, only the following building components were determined to contain toxic levels of lead (greater than 1.0 milligrams of lead per square centimeter of paint [mg/cm²]):

Table 3
Lead Painted Building Components

Building Component	Location	Reading (mg/cm ²)	Defective?
Exterior Window Sash	East Side of Building (C)	1.1	Yes
Interior Wood Wall	Annex Garage	>9.9	No

Refer to *Appendix D* for the lead testing field data sheets and diagrams.

3.3 Dust Wipe Samples Results

Representative dust wipe samples were collected inside the Site structure to evaluate whether a lead dust hazard exists. The sample numbers, locations, and results are as follows:

Table 4
Lead Dust Wipe Sample Results

Sample No.	Sample Location	Results*
050714UA-03	Bedroom 2—Floor	<10 µg/ft ²
050714UA-04	Bedroom 2—Window Sill	<40 µg/ft ²
050714UA-05	Office (Room 4)—Floor	<10 µg/ft ²
050714UA-06	Office (Room 4)—Floor <i>duplicate sample</i>	46 µg/ft ²
050714UA-07	Office (Room 4)—Window Sill	370 µg/ft ²
050714UA-08	Kitchen (Room 8)—Window Sill	<40 µg/ft ²
050714UA-09	Kitchen (Room 8)—Floor	<10 µg/ft ²
050714UA-10	Loft (Room 9)—Window Sill	<40 µg/ft ²
050714UA-11	Loft (Room 9)—Floor	<10 µg/ft ²
050714UA-12	Field Blank	<10 µg/ft ²
050714UA-13	Field Blank	<10 µg/ft ²

Note: µg/ft² = micrograms of lead per square foot

Dust wipe samples were collected from window sill and floor locations as delineated on our chain of custody form. The dust wipe sampling was conducted in accordance with the protocol outlined in the document “Lead Testing Procedures and Equipment” (refer to *Appendix C*). Sample results were compared to State of Connecticut re-occupancy standards for dust as follows:

- 40 µg/ft² for floors

- 250 µg/ft² for window sills

The analytical sample results and chain of custody forms are provided as *Appendix E* in this report.

3.4 Lead in Soil Sample Results

A representative composite soil sample was collected of the bare soil area along the exterior drip line of the Site structure to evaluate whether a lead in soil hazard exists. The sample numbers, locations, and results are as follows:

Table 5
Soil Sample Results

Sample No.	Location	Results*
050714UA-14	A-Side Composite, Drip Line	740 mg/kg
050714UA-15	B-Side Composite, Drip Line	66 mg/kg
050714UA-15	D-Side Composite, Drip Line	160 mg/kg

*Results reported in mg/kg = milligrams per kilogram (or ppm)

The soil sampling was conducted in accordance with the protocol outlined in the document "Lead Testing Procedures and Equipment" (refer to *Appendix C*).

The analytical sample results and locations are provided as *Appendix F* in this report.

3.5 Lead in Drinking Water Sample Results

Representative drinking water samples (first draw and two-minute flush) were collected from the kitchen faucet at the Site structure to evaluate whether a lead in drinking water hazard exists.

The analytical results of the samples were 0.129 milligrams per liter (mg/L) for the first draw and 0.008 mg/L for the two minute flush for lead in drinking water.

The analytical sample results and their locations are provided as *Appendix G* in this report.

3.6 Conclusions

The following building components were determined to be coated with toxic levels of lead in paint:

- Window Sash—C Side
- Garage Interior Wall

Exterior defective LBP identified on the window and door systems, and exterior front porch components can be addressed with interim controls that consist of scraping the defective LBP and encapsulating the painted surface with a CTDPH-approved encapsulant.

If these LBP-containing building components are to be demolished during renovations, a representative sample of the demolition waste stream must be collected and analyzed by TCLP to determine off-site disposal requirements.

Dust wipe sample results were above the State of Connecticut standard for window sill and floor surfaces in the office (Room 4); a lead dust hazard does exist in the areas tested. Lead dust located on the floor and window sill surfaces within the office (Room 4) must be cleaned to below the State of Connecticut clearance standards of 40 µg/ft² for floors and 250 µg/ft² for window sills. Additionally, the floors and window sills that sampled need to be sampled or assumed to contain lead dust above the clearance standards.

Soil sample results were above the CTDPH standard for lead in soil of 400 mg/kg; a lead in soil hazard does exist in the areas tested. Impermanent surface coverings may be used to treat lead-contaminated soil if applied. Examples of acceptable impermanent coverings include: gravel, bark, sod, and artificial turf.

The first draw lead in drinking water sample result indicates the lead in water at a concentration of 0.129 mg/L. The two-minute flush lead in drinking water sample result indicates lead in water at a concentration of 0.008 mg/L. A lead in drinking water hazard does exist in the residence as the results were above the 0.015 mg/L threshold.

Note that OSHA has not established a level of lead in a material below which Title 29 CFR, Part 1926.62 does not apply. The Contractor shall comply with exposure assessment criteria, interim worker protection, and other requirements of the regulation as necessary to protect workers and building occupants.

For purposes of complying with the EPA RRP, a comprehensive lead inspection of the entire structure or targeted areas scheduled for renovation is necessary to determine if the RRP rule is applicable. A comprehensive lead inspection includes testing representative coated surfaces of each building component in each room or room equivalent for lead in paint content. All similar building components to the surface tested on a per room basis shall be considered as having the same paint (e.g., if more than one window or door in a room - typically only one is tested but remaining must be assumed to be the same as the one tested). **This inspection was performed as a comprehensive inspection of all representative surfaces within the residence that are scheduled to be disturbed and can be utilized to determine applicability requirements for the RRP rule on surfaces tested.**

Those surfaces which contain lead paint are subject to RRP work practice and training requirements if more than de-minimus amounts are disturbed in renovation or for projects involving window replacement. Those surfaces that do not contain LBP are not subject to the RRP requirements. If a specific building component or surface is not identified as having been tested for LBP, it should be presumed to contain LBP unless testing indicates otherwise. Contractors should be aware that the threshold limit of 1.0 mg/cm² for purposes of RRP requirements is not recognized by OSHA and is subject to the "Lead in Construction" regulation

4 Assessment of PCB-Containing Fluorescent Ballasts

Fluorescent light ballasts manufactured prior to 1979 may contain capacitors that contain PCBs. Ballasts installed as late as 1985 may contain PCB capacitors. Fluorescent light ballasts that are not labeled as "No-PCBs" must be assumed to contain PCBs unless proven otherwise by quantitative analytical testing. Capacitors in fluorescent light ballasts labeled as non-PCB-containing may contain diethylhexyl phthalate (DEHP). DEHP was the primary substitute to replace PCBs for small capacitors in fluorescent lighting ballasts in use until 1991. DEHP is a toxic substance, a suspected carcinogen and is listed under the EPA Resource Conservation and Recovery Act (RCRA) and the Superfund law as a hazardous waste. Therefore, Superfund liability exists for land filling both PCB and DEHP-containing light ballasts. These listed materials are considered hazardous waste under RCRA and require special handling and disposal requirements.

4.1 Methodology

On April 7, 2014, EnviroScience representative Mr. Hobbins performed a visual inspection of representative fluorescent light fixtures to identify possible PCB-containing ballasts. The inspection involved visually inspecting labels on representative light ballasts to identify dates of manufacture and labels indicating "No PCB's". Ballasts manufactured after 1991 were not listed as a PCB or DEHP-containing ballast, and not quantified for disposal. Ballasts without a "No PCB's" label are presumed to be PCB waste, and must be segregated for proper removal, packaging, transport and disposal as PCB waste. Ballasts with date labels indicating manufacture prior to 1991 that indicate "No PCB's" are presumed to contain DEHP, and must be segregated for proper removal, packaging, transport, and disposal as non-PCB hazardous waste. The disposal requirements are slightly varied, and costs are slightly less for DEHP than PCB-containing light ballasts.

4.2 Results

Several of the light fixtures that were examined were labeled neither with the manufacturer's information, nor with a "No PCB's" label. However during the inspection, some types of light ballasts were labeled with a "No PCB's" label. Therefore there is a mixture of assumed PCB-containing and non-PCB containing light ballasts within the Site building areas inspected. .

It is estimated that a total of approximately 10 light ballasts exist within the Site structure that were neither labeled with the manufacturer's information, nor with a "No PCB's" label.

4.3 Conclusions

If the renovation activities will disturb the materials, the ballasts labeled "No PCBs" should be properly recycled as PCBs. The remaining ballasts that are labeled "No PCBs" should be properly recycled as assumed DEHP-containing waste.

5 Assessment of Mercury-Containing Devices

Fluorescent lamps/tubes are presumed to contain mercury vapor, which is a hazardous substance to both human health and the environment. Thermostatic controls and electrical switch gear may contain a vial or bulb of mercury associated with the control. Mercury-containing equipment is regulated for proper disposal by the EPA RCRA hazardous waste regulations. Mercury lamps according to the EPA are considered a universal waste requiring all fluorescent lamps/tubes to be recycled or disposed as hazardous waste.

5.1 Methodology

On April 7, 2014, EnviroScience's representative Mr. Hobbins performed a visual inspection and inventory of mercury-containing lamps/tubes, thermostats, gauges and switches.

5.2 Results

Approximately 20 light bulbs were observed during the visual inspection. No thermostats, switches, or gauges were observed within the structure.

5.3 Conclusions

The mercury-containing light bulbs should be properly recycled or disposed as universal waste prior to disturbance.

6 Mold Visual Assessment

On April 8, 2014, EnviroScience representative Mr. Hobbins performed a visual assessment for the presence of suspect mold and water intrusion.

6.1 Observations

No suspected mold growth was identified on building materials observed within the Site structure at the time of this inspection.

7 Airborne Radon Information, Sampling and Procedure

7.1 Radon Facts and Health Effects

Radon is a naturally-occurring radioactive gas produced by the natural breakdown (decay) of uranium which is found in soil and rock throughout the US. Radon gas travels through soil and enters buildings through cracks and other penetrations in building foundations. Eventually the gas itself decays into

radioactive particles (decay products) that can become trapped in the lungs during human respiration. As these particles in turn decay they release small bursts of radiation which can damage lung tissue and lead to lung cancer over the course of a person's lifespan.

EPA studies have determined that radon gas concentrations in outdoor air average approximately 0.4 picoCuries per liter of air (pCi/L). However, radon and its decay products can accumulate to a much higher concentration inside a building. The EPA has adopted a recommended action level of 4.0 pCi/L; equal to or above which the EPA recommends that building owners take action to reduce the level of airborne radon with the building.

Radon is a colorless, odorless and tasteless gas, and thus, the only way to know whether or not an elevated level of radon gas is present in a building is to test the air for radon gas. Each frequently occupied room that is in contact with the lowest living level of the building should be measured, as even adjacent rooms can have significantly different levels of radon.

Again, radon is a known human carcinogen. Prolonged exposure to elevated radon concentrations causes an increased risk of lung cancer. Like other environmental pollutants, there is some uncertainty about the magnitude of radon health risks. However, scientists are more certain about radon risks than risks from most other cancer-causing environmental pollutants as estimates of radon risk are based on studies of cancer in humans (underground miners). Additional studies on more typical, non-occupationally exposed, populations are underway.

EPA estimates that radon may cause about 14,000 lung cancer deaths in the US each year, with a range of 7,000 to 30,000. The US Surgeon General has warned that radon gas is the second-leading cause of lung cancer deaths after smoking, and is the leading cause among non-smokers.

7.2 Airborne Radon Sampling Methodology

From April 8, 2014 to April 10, 2014, EnviroScience representatives deployed passive radon gas detection canisters in limited areas within the Site structure. The canisters were retrieved at least 48-hours, but not later than 96-hours later. The canisters were supplied by Radon Testing Corporation of America (RTCA).

It is recommended that such canisters be placed at least 20-inches from the floor and 12 inches away from exterior walls. Also, it is recommended that the canisters not be placed near drafts resulting from Heating, Ventilating and Air Conditioning (HVAC) intakes and returns, doors, and at least 36-inches from windows. Also, canisters should not be exposed to direct sunlight, be covered up, or otherwise disturbed during the testing period. A closed building condition is also utilized for 12-hours prior to testing being conducted.

Sample analysis was performed by RTCA; results are included in *Appendix F*.

7.3 Airborne Radon Quality Assurance Procedure

EPA strongly recommends that quality assurance measurements are included in radon measurement studies. Quality assurance measurements include side-by-side canisters (duplicates), and unexposed control canisters (blanks).

Duplicates are pairs of canisters deployed in the same location, side-by-side, for the same measurement period. Duplicates are placed in at least ten percent of all sampling locations. These duplicate canisters are stored, deployed, removed, and shipped to the laboratory for analysis in the same manner as the other canisters. If either or both of the analyses in a duplicate pairing is above the EPA standard of 4.0 pCi/L, the relative percent difference (RPD) between the two tests must be determined. If the allowable difference is exceeded, the test is determined to be invalid and a new duplicate test must be run. If both canister results are below the EPA standard then the RPD is not calculated since, despite any disparity, both results are below the EPA standard.

Blanks are utilized to determine whether the manufacturing, shipping, storage, and processing of the canisters has affected the accuracy of airborne radon gas sampling procedures. Blanks are unopened, unexposed canisters that are deployed with and shipped with the exposed canisters, so the processing laboratory treats them without bias. The number of blanks is at least five percent of the total number of canisters deployed, up to a maximum of 25 canisters.

7.4 Airborne Radon Analytical Results

Four canisters, including one duplicate and one blank, were deployed in target locations within the Site structure during sampling that was performed April 8, 2014, to April 10, 2014. The concentrations of radon gas in the samples during the initial assessment ranged from 0.1 pCi/L to 2.6 pCi/L. The EPA recommended action level for indoor radon gas is 4.0 pCi/L.

In *Table 6* below, the locations and results of quality control duplicate tests are listed for the sampling conducted from April 8, 2014 to April 10, 2014:

Table 6
Duplicate Samples Results – April 8, 2014 – April 10, 2014

Location	Canister Numbers	Radon Concentration (pCi/Liter)			Relative Percent Difference (RPD, %)
		Sample	Sample Duplicate	Sample Average	
Bedroom 2	2299423 & 2313946	0.5	0.4	0.45	Percent Difference Not Needed (No Concentrations Above 4.0 pCi/Liter)

Note Duplicate testing results were satisfactory.

In *Table 7* below, the locations and results of quality control blank tests are listed for sampling conducted from April 8 2014 to April 10, 2014:

Table 7
Blank Samples Results – April 8, 2014 – April 10, 2014

Location	Canister Numbers	Radon Concentration (pCi/Liter)
Office	2314400	0.4

Note Blank testing results were satisfactory.

In *Table 8* below, the locations, canister numbers, and radon concentrations are listed for the airborne radon assessment conducted from April 8, 2014 to April 10, 2014:

Table 8
Radon Sampling Results – April 8, 2014 – April 10, 2014

Location	Canister Numbers	Radon Concentration (pCi/Liter)
Bedroom	2299423	0.5
Office	2314120	0.2


7.5 Conclusions

During the course of the initial radon gas assessment, four sampling canisters, including one duplicate and one blank, were placed in targeted locations within Site structure. Of the four samples analyzed, each of the samples collected were below EPA recommended action level of 4.0 pCi/L. No further action regarding radon gas is required.

Report prepared by Environmental Technician Robert Hobbins.

Reviewed by:


Kevin McCarthy
Project Manager


Timothy M. Downey
Senior Project Manager

Appendix A

Fuss & O'Neill EnviroScience State Licenses, Certifications and Accreditations

0001780 PP **PRGRT T7 0 1284 08040
ULKENS AUGUSTE
 148 HARTFORD RD
 C/O FUSS & O'NEIL ENVIRO SCIENCE
 MANCHESTER CT 06040-5992

Dear Licensed/Certified Professional:
 Attached you will find your validated license/certification
 for the coming year. Should you have any questions about
 your license/certification renewal, please do not hesitate to
 write or call.

Department of Public Health (203) 686-7013
 P.O. Box 34000
 H.S. 20000
 Hartford, CT 06134-0000
<http://www.dph.state.ct.us>

Sincerely,

John P. Miller

JOHN P. MILLER, M.D., M.P.H.
 Commissioner of Public Health

INSTRUCTIONS:

1. Detach and sign each of the cards on this form.
2. Display the large card in a prominent place in your office or place of business.
3. The wallet card is for you to carry on your person. If you do not wish to carry the wallet card, place it in a secure place.

4. The employer's copy is for persons who must demonstrate current licensure/certification in order to retain employment or privileges. The employer's card is to be presented to the employer and kept by them as a part of your personnel file. Only one copy of this card can be supplied to you.

STATE OF CONNECTICUT
DEPARTMENT OF PUBLIC HEALTH
WALTON S. DEER, M.D., M.P.H.
Commissioner of Public Health
WALTON S. DEER, M.D., M.P.H.
Commissioner of Public Health

Auguste Ulkens

EMPLOYER'S COPY
STATE OF CONNECTICUT
DEPARTMENT OF PUBLIC HEALTH
WALTON S. DEER, M.D., M.P.H.
Commissioner of Public Health

NAME: ULKENS AUGUSTE
VALIDATION NO.: 03-037410 **EXPIRATION DATE:** 08/30/14
DATE OF ISSUE: 08/30/14

John P. Miller

WALTON S. DEER, M.D., M.P.H.
Commissioner of Public Health
WALTON S. DEER, M.D., M.P.H.
Commissioner of Public Health

NAME: ULKENS AUGUSTE
VALIDATION NO.: 03-037410 **EXPIRATION DATE:** 08/30/14
DATE OF ISSUE: 08/30/14

John P. Miller

Fuss & O'Neill EnviroScience, LLC

146 Hartford Road, Manchester, CT 06040 – (860) 646-2469

This is to certify that

Ulkens Auguste
xxx-xx-6277


has successfully completed the
4 Hr. Asbestos Inspector Refresher
Asbestos Accreditation under TSCA Title II
40 CFR Part 763



John Rowinski, Principal Instructor

January 6, 2014
Date of Course

January 6, 2014
Examination Date



Robert L. May, Jr., Training Manager

AI-R-01/14-4
Certificate Number

January 6, 2015
Expiration Date

0001768 PP **PRST T7 0 1264 08040
ULKENS AUGUSTE
 146 HARTFORD RD
 C/O FUSS & O'NEIL ENVIRO SCIENCE
 MANCHESTER CT 06040-5882

Dear Licensed/Certified Professional:
 Attached you will find your validated license/certification for the coming year. Should you have any questions about your license/certification renewal, please do not hesitate to write or call.

Department of Public Health (844) 645-7689
 P.O. Box 35000
 Hartford, CT 06155-0000
<http://www.hartford.gov>

Sincerely,

Just Malin

JUST MALIN, MD, MPH, FRCPC, FRCPC
 DEPARTMENT OF PUBLIC HEALTH

INSTRUCTIONS:

1. Detach and sign each of the cards on this form.
2. Display the large card in a prominent place in your office or place of business.
3. The wallet card is for you to carry on your person. If you do not wish to carry the wallet card, place it in a secure place.

4. The employer's copy is for persons who must demonstrate current licensure/certification in order to retain employment or privileges. The employer's card is to be presented to the employer and kept by them as a part of your personnel file. Only one copy of this card can be supplied to you.



Fuss & O'Neill EnviroScience, LLC

146 Hartford Road, Manchester, CT 06040 – (860) 646-2469

This is to certify that

Ulkens Auguste

xxx-xx-6277

has successfully completed the

8 Hour Lead Inspector Risk Assessor Refresher Course

(Approved per Sec. 20-477, CT General Statutes)

Under civil and criminal penalties of law for the making or submission of false or fraudulent statements or representations (U.S.C. 1001 and 15 U.S.C. 2615), I certify that this training complies with all applicable requirements of Title IV of TSCA, 40 CFR part 745 and any other applicable Federal, State, or local requirements.



Brian Samos, Principal Instructor

February 20 & 25, 2014

Date of Course

February 25, 2014

Examination Date



Robert L. May, Jr., Training Manager

LIRA-R-02/14-1

Certificate Number

February 25, 2015

Expiration Date

0001068 FP **PRSR T6 0 0554 06040
JOHN R. HOBBS
 C/O FUSS & O'NEILL ENVIROSCIENCE, LLC
 148 HARTFORD ROAD
 MANCHESTER CT 06040

Dear Licensed/Certified Professional,
 Attached you will find your validated license/certification for the coming year. Should you have any questions about your license/certification renewal, please do not hesitate to write or call:

Department of Public Health (508) 253-7000
 P.O. Box 34000
 H.S. 21000A <http://www.dph.state.ct.us>
 Hartford, CT 06101-0000

Sincerely,

Joel Muller

JOEL MULLER, MD, MPH, DPH, COMMERCIAL
 DEPARTMENT OF PUBLIC HEALTH

INSTRUCTIONS:

1. Detach and sign each of the cards on this form.
2. Display the large card in a prominent place in your office or place of business.
3. The wallet card is for you to carry on your person. If you do not wish to carry the wallet card, place it in a secure place.

4. The employer's copy is for persons who must demonstrate current licensure/certification in order to retain employment or privileges. The employer's card is to be presented to the employer and kept by them as a part of your personnel file. Only one copy of this card can be supplied to you.

STATE OF CONNECTICUT
 DEPARTMENT OF PUBLIC HEALTH
 PURSUANT TO THE PROVISIONS OF THE GENERAL STATUTES OF CONNECTICUT
 THIS INDIVIDUAL NAMED BELOW IS LICENSED
 IN THE PROFESSION OF
ASBESTOS CONSULTANT-INSPECTOR

NAME
JOHN R. HOBBS

LICENSE NO.
000700

CURRENT THROUGH
01/31/15

VALIDATION NO.
03-706142

John R. Hobbs *Joel Muller*

EMPLOYER'S COPY
 STATE OF CONNECTICUT
 DEPARTMENT OF PUBLIC HEALTH
 NAME
JOHN R. HOBBS

VALIDATION NO.
03-706142

LICENSE NO.
000700

CURRENT THROUGH
01/31/15

PROFESSION
ASBESTOS CONSULTANT-INSPECTOR

John R. Hobbs *Joel Muller*

WALLET CARD
 STATE OF CONNECTICUT
 DEPARTMENT OF PUBLIC HEALTH
 NAME
JOHN R. HOBBS

VALIDATION NO.
03-706142

LICENSE NO.
000700

CURRENT THROUGH
01/31/15

PROFESSION
ASBESTOS CONSULTANT-INSPECTOR

John R. Hobbs *Joel Muller*

Russ & O'Neill Environmental Science, LLC

146 Hartford Road, Manchester, CT 06040 - (860) 646-2469

This is to certify that

Robert Robert Elabbas

XXX-XX-6853

has successfully completed the

4 Hr. Asbestos Inspection Refresher

Asbestos Accreditation under NIOSH Title II

40 CFR Part 763

John Lowinski
John Lowinski, Principal Instructor

Robert L. May, Jr.
Robert L. May, Jr., Training Manager

September 4, 2013

Date of Course

AT-R-09/13-6

Certificate Number

September 4, 2013

Expiration Date & Grade

September 4, 2014

Expiration Date

John R. Hobbins
C/O FUSS & O'NEILL ENVIROSCIENCE, LLC
146 HARTFORD ROAD
MANCHESTER, CT 06040

Dear Licensed/Certified Professional,
Attached you will find your requested license/certification
for the coming year. Should you have any questions about
your license/certification renewal, please do not hesitate to
write or call:

Department of Public Health
P.O. Box 249908
M.S. #12100A
Hartford, CT 06134-0908

(860) 509-7603

<http://www.dph.state.ct.us>

Jewel Mullen




Jewel Mullen

JEWEL MULLEN, MD, MPH, MPA, COMMISSIONER
DEPARTMENT OF PUBLIC HEALTH

INSTRUCTIONS:

1. Detach and sign each of the cards on this form.
2. Display the name card in a prominent place in your office or place of business.
3. The name card is for you to verify the person, if you do not wish to carry the name card, place it in a display glass.

4. The name card is for persons who need identification in order to receive employment or privileges. The name card is to be presented to the employer and kept by them as a part of your personnel file. Only one copy of the card can be supplied to you.



CERTIFICATE OF ACHIEVEMENT

This certifies that

John Robert Hobbins

97 Montowese Street, Branford, CT 06405
000-00-6853

has successfully completed the

INSPECTOR REFRESHER

*Training Course
conducted by
Cardno ATC*

73 William Franks Drive
West Springfield, MA 01089
(413) 781-0070

Neal B. Frenken

Principal Instructor: Neal Frenken

January 30, 2014
Date of Course

January 30, 2014
Exam Date

CTLR-205
Certificate Number

January 30, 2015
Expiration Date

Gregory J. Mersch

Training Manager: Gregory Mersch

*Training received complies with the requirements of the
Connecticut Department of Public Health pursuant to Section
477 of the Connecticut General Statutes.*

Appendix B

Asbestos Sample Results and Chain of Custody Forms



FUSS & O'NEILL
EnviroScience, LLC

041416025

www.fando.com

146 Hartford Road, Manchester, CT 06040

Phone (860)646-2469 Fax (860) 649-6883

SAMPLE LOG FOR ASBESTOS BULKS

Sheet 1 of 4

Project Name: QA Residential Rehab 35 old Dam Rd. 31 Westland Street, Fairfield, CT

Project No. 20140277.A6E

Building: 31 Westland Street

Project Manager: McCarthy

Sample ID	Sample Location	Material	Result (%)
0408BH01A	Main Floor	Textured Ceiling Paint	<p><i>None Detected</i></p> <p>RECEIVED EMSL N. J. APR 15 A 11:22</p>
0408BH01B	Main Floor	Textured Ceiling Paint	
0408BH01C	Main Floor	Textured Ceiling Paint	
0408BH01D	Main Floor	Textured Ceiling Paint	
0408BH01E	Main Floor	Textured Ceiling Paint	
0408BH01F	Main Floor	Textured Ceiling Paint	
0408BH01G	Main Floor	Textured Ceiling Paint	
0408BH02A	Main Floor	Sheetrock	
0408BH02B	Crawlspace	Sheetrock	
0408BH03A	Main Floor	Taping/Joint Compound	
0408BH03B	Crawlspace	Taping/Joint Compound	
0408BH04	Crawlspace	Sheetrock & Taping/Joint Compound Composite	<i><1% chrysotile</i>
0408BH05A	Crawlspace	White Backing on Fiberglass Insulation	<i>None Detected</i>
0408BH05B	Crawlspace	White Backing on Fiberglass Insulation	
0408BH06A	Main Floor Foyer	Red Slate Floor Tile	

Analysis Method: ☒ PLM ☐ Other

Turnaround Time 24 hr

Based on the turnaround time indicated above, analyses are due to EnviroScience on or before this date: _____. Please call the EnviroScience Laboratory if analyses will be late at (860) 646-2469.

Fax Results to the EnviroScience Laboratory at: 888-838-1160.

Special Instructions: Stop analysis on first positive sample in each homogeneous set of samples unless otherwise noted. Do not layer samples unless indicated. EPA 400 Point Count all samples of content <4%, positive stop on all point counts.

Samples collected by: R. Hollins Date: 4-8-14 Time: _____

Samples [Rec'd] [Sent by] BLH Date: 4-14 Time: _____

Samples Received by: AK CMSL EX Date: 4/15/14 Time: 1015

Shipped To: ☒ EMSL State NJ ☐ Other _____

Method of Shipment: ☒ FedEx ☐ Other _____

SB



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

Phone (860) 646-2469 Fax (860) 649-6883

SAMPLE LOG FOR ASBESTOS BULKS

Sheet 2 of 4

Project Name: QA Residential Rehab - 35 old Dam Rd

Project No. 20140277.A6E

Building: 31 Westland Street

Project Manager: McCarthy

Sample ID	Sample Location	Material	Result (%)
0408BH06B	Main Floor Foyer	Red Slate Floor Tile	None Detected
0408BH07A	Main Floor Foyer	Red Slate Floor Tile Grout	
0408BH07B	Main Floor Foyer	Red Slate Floor Tile Grout	
0408BH08A	Main Floor Foyer	Red Slate Floor Tile Glue	
0408BH08B	Main Floor Foyer	Red Slate Floor Tile Glue	
0408BH09A	Main Floor Master Bath	White/Green/Blue Sheet Flooring	
0408BH09B	Main Floor Master Bath	White/Green/Blue Sheet Flooring	
0408BH10A	Main Floor Master Bath	Sheet Flooring Glue	
0408BH10B	Main Floor Master Bath	Sheet Flooring Glue	
0408BH11A	Main Floor Master Bath	Brown Cove Base	
0408BH11B	Main Floor Master Bath	Brown Cove Base	
0408BH12A	Main Floor Master Bath	Cove Base Glue	
0408BH12B	Main Floor Master Bath	Cove Base Glue	
0408BH13A	Main Floor Foyer Bath	Self-Stick Floor Tile	
0408BH13B	Main Floor Foyer Bath	Self-Stick Floor Tile	

Analysis Method: ☒ PLM ☐ Other

Turnaround Time 24 hr

Based on the turnaround time indicated above, analyses are due to EnviroScience on or before this date: _____. Please call the EnviroScience Laboratory if analyses will be late at (860) 646-2469.

Fax Results to the EnviroScience Laboratory at: 888-838-1160.

Special Instructions: Stop analysis on first positive sample in each homogeneous set of samples unless otherwise noted. Do not layer samples unless indicated. EPA 400 Point Count all samples of content <4% positive stop on all point counts.

Samples collected by: BA Date: 4-8-14 Time: _____

Samples [Rec'd] [Sent by] BA] Date: 4-14] Time: _____

Samples Received by: _____ Date: _____ Time: _____

Shipped To: ☒ EMSL State NJ ☐ Other _____

Method of Shipment: ☒ FedEx ☐ Other _____



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

Phone (860)646-2469 Fax (860) 649-6883

SAMPLE LOG FOR ASBESTOS BULKS

Sheet 2 of 4

Project Name: QA Residential Rehab-31 Westland Street, Fairfield, CT

Project No. 20140277.A6E

Building: 31 Westland Street

Project Manager: McCarthy

Sample ID	Sample Location	Material	Result (%)
0408BH14A	Main Floor Master Bath	Ceramic Tile	None Detected
0408BH14B	Main Floor Master Bath	Ceramic Tile	
0408BH15A	Main Floor Master Bath	Ceramic Tile Grout	
0408BH15B	Main Floor Master Bath	Ceramic Tile Grout	
0408BH16A	Main Floor Master Bath	Ceramic Tile Glue	
0408BH16B	Main Floor Master Bath	Ceramic Tile Glue	
0408BH17A	2nd Floor Kitchen	Self-Stick Linoleum Floor Tile	None Detected
0408BH17B	2nd Floor Kitchen	Self-Stick Linoleum Floor Tile	
0408BH18A	2nd Floor Laundry	Grey Top Layer Self Stick Floor Tile	
0408BH18B	2nd Floor Laundry	Grey Top Layer Self Stick Floor Tile	
0408BH19A	2nd Floor Laundry	Bottom Layer Tan Sheet Flooring	
0408BH19B	2nd Floor Laundry	Bottom Layer Tan Sheet Flooring	
0408BH20A	Exterior of Building	Exterior Window Glazing Compounds	None Detected
0408BH20B	Exterior of Building	Exterior Window Glazing Compounds	
0408BH20C	Exterior of Building	Exterior Window Glazing Compounds	

Analysis Method: ☒ PLM ☐ Other

Turnaround Time 24 hr

Based on the turnaround time indicated above, analyses are due to EnviroScience on or before this date: _____. Please call the EnviroScience Laboratory if analyses will be late at (860) 646-2469.

Fax Results to the EnviroScience Laboratory at: 888-838-1160.

Special Instructions: Stop analysis on first positive sample in each homogeneous set of samples unless otherwise noted. Do not layer samples unless indicated. EPA 400 Point Count all samples of content <4%, positive stop on all point counts.

Samples collected by: R.H. Date: 4-8-14 Time: _____

Samples [Rec'd][Sent by] BH Date: 4-14 Time: _____

Samples Received by: _____ Date: _____ Time: _____

Shipped To: ☒ EMSL State NJ ☐ Other _____

Method of Shipment: ☒ FedEx ☐ Other _____



FUSS & O'NEILL
EnviroScience, LLC

041410025

www.fando.com

146 Hartford Road, Manchester, CT 06040

Phone (860)646-2469 Fax (860) 649-6883

SAMPLE LOG FOR ASBESTOS BULKS

Sheet 4 of 4

Project Name: QA Residential Rehab-31 Westland Street, Fairfield, CT Project No. 20140277.A6E

Building: 31 Westland Street Project Manager: McCarthy

Sample ID	Sample Location	Material	Result (%)
0408BH21A	Exterior of Building	Paper Vapor Barrier behind Siding	None Detected
0408BH21B	Exterior of Building	Paper Vapor Barrier behind Siding	
0408BH22A	Exterior Roof	Top Layer Roof Shingle	
0408BH22B	Exterior Roof	Top Layer Roof Shingle	
0408BH23A	Exterior Roof	Bottom Layer Roof Shingle	
0408BH23B	Exterior Roof	Bottom Layer Roof Shingle	
0408BH24A	Exterior Garage	Exterior Window Glazing Compounds	
0408BH24B	Exterior Garage	Exterior Window Glazing Compounds	
0408BH24C	Exterior Garage	Exterior Window Glazing Compounds	
0408BH25A	Exterior Garage	Concrete Block	
0408BH25B	Exterior Garage	Concrete Block	
0408BH26A	Exterior Garage	Concrete Block Grout	
0408BH26B	Exterior Garage	Concrete Block Grout	

2014 APR 15 A 11:22
REC'D
EMSL
CINNAMINSON, N.J.

Analysis Method: ☒ PLM ☐ Other

Turnaround Time 24 hr

Based on the turnaround time indicated above, analyses are due to EnviroScience on or before this date: _____. Please call the EnviroScience Laboratory if analyses will be late at (860) 646-2469.

Fax Results to the EnviroScience Laboratory at: 888-838-1160.

Special Instructions: Stop analysis on first positive sample in each homogeneous set of samples unless otherwise noted. Do not layer samples unless indicated. EPA 400 Point Count all samples of content <4%, positive stop on all point counts.

Samples collected by: BH Date: 4-8-14 Time: _____

Samples [Rec'd][Sent by] [BH] Date: 4-14 Time: _____

Samples Received by: _____ Date: _____ Time: _____

Shipped To: ☒ EMSL State NJ ☐ Other _____

Method of Shipment: ☒ FedEx ☐ Other _____

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (800) 220-3675 / (856) 786-5974

<http://www.EMSL.com> cinnaslab@EMSL.com

EMSL Order: 041410025
CustomerID: ENVI54
CustomerPO:
ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
0408BH01A 041410025-0001	MAIN FLOOR - TEXTURED CEILING PAINT	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH01B 041410025-0002	MAIN FLOOR - TEXTURED CEILING PAINT	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH01C 041410025-0003	MAIN FLOOR - TEXTURED CEILING PAINT	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH01D 041410025-0004	MAIN FLOOR - TEXTURED CEILING PAINT	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH01E 041410025-0005	MAIN FLOOR - TEXTURED CEILING PAINT	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH01F 041410025-0006	MAIN FLOOR - TEXTURED CEILING PAINT	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH01G 041410025-0007	MAIN FLOOR - TEXTURED CEILING PAINT	White Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH02A 041410025-0008	MAIN FLOOR - SHEETROCK	Gray Fibrous Homogeneous	15% Cellulose	85% Non-fibrous (other)	None Detected

Analyst(s)

Brett Poulton (31)
Chelsey Bilhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-fragile organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%.

Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367

Initial report from 04/16/2014 07:04:32

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077
Phone/Fax: (800) 220-3675 / (856) 786-5974
<http://www.EMSL.com> cinnaslab@EMSL.com

EMSL Order: 041410025
CustomerID: ENVI54
CustomerPO:
ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos	
			% Fibrous	% Non-Fibrous	% Type	
0408BH02B 041410025-0009	CRAWLSPACE - SHEETROCK	Brown/Gray Fibrous Homogeneous	15% Cellulose	85% Non-fibrous (other)		None Detected
0408BH03A 041410025-0010	MAIN FLOOR - TAPING/ JOINT COMPOUND	Brown/White Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (other)		None Detected
0408BH03B 041410025-0011	CRAWLSPACE - TAPING/ JOINT COMPOUND	Tan Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (other)		None Detected
0408BH04 041410025-0012	CRAWLSPACE - SHEETROCK & TAPING/ JOINT COMPOUND	Brown/Gray/Tan Fibrous Homogeneous	15% Cellulose 2% Glass	83% Non-fibrous (other)	<1% Chrysotile	
0408BH05A 041410025-0013	CRAWLSPACE - WHITE BACKING ON FIBERGLASS INSULATION	White Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected
0408BH05B 041410025-0014	CRAWLSPACE - WHITE BACKING ON FIBERGLASS INSULATION	White Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected
0408BH06A 041410025-0015	MAIN FLOOR FOYER - RED SLATE FLOOR TILE	Red Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected
0408BH06B 041410025-0016	MAIN FLOOR FOYER - RED SLATE FLOOR TILE	Red Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected

Analyst(s)

Brett Poulton (31)
Chelsey Billhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%
Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367

Initial report from 04/16/2014 07:04:32

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077
Phone/Fax: (800) 220-3875 / (856) 786-5974
<http://www.EMSL.com> cinnaslab@EMSL.com

EMSL Order: 041410025
CustomerID: ENVI54
CustomerPO:
ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
0408BH07A 041410025-0017	MAIN FLOOR FOYER - RED SLATE FLOOR TILE GROUT	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH07B 041410025-0018	MAIN FLOOR FOYER - RED SLATE FLOOR TILE GROUT	Gray/Red Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH08A 041410025-0019	MAIN FLOOR FOYER - RED SLATE FLOOR TILE GLUE	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH08B 041410025-0020	MAIN FLOOR FOYER - RED SLATE FLOOR TILE GLUE	Tan/Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH09A 041410025-0021	MAIN FLOOR MASTER BATH - WHITE/ GREEN/ BLUE SHEET FLOORING	White/Blue/Green Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH09B 041410025-0022	MAIN FLOOR MASTER BATH - WHITE/ GREEN/ BLUE SHEET FLOORING	White/Blue/Green Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH10A 041410025-0023	MAIN FLOOR MASTER BATH - SHEET FLOORING GLUE	Brown Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected

Analyst(s)

Brett Poulton (31)
Chelsey Bilhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-fragile organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%
Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367

Initial report from 04/16/2014 07:04:32

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (800) 220-3875 / (856) 786-5974

<http://www.EMSL.com>cinnaslab@EMSL.com

EMSL Order: 041410025

CustomerID: ENVI54

CustomerPO:

ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
0408BH10B 041410025-0024	MAIN FLOOR MASTER BATH - SHEET FLOORING GLUE	Yellow/Clear Non-Fibrous Homogeneous	3% Cellulose	97% Non-fibrous (other)	None Detected
0408BH11A 041410025-0025	MAIN FLOOR MASTER BATH - BROWN COVE BASE	Brown Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH11B 041410025-0026	MAIN FLOOR MASTER BATH - BROWN COVE BASE	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH12A 041410025-0027	MAIN FLOOR MASTER BATH - COVE BASE GLUE	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH12B 041410025-0028	MAIN FLOOR MASTER BATH - COVE BASE GLUE	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH13A 041410025-0029	MAIN FLOOR FOYER BATH - SELF-STICK FLOOR TILE	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH13B 041410025-0030	MAIN FLOOR FOYER BATH - SELF-STICK FLOOR TILE	Gray/White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected

Analyst(s)

Brett Poulton (31)
Chelsey Bilhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%
Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-RIHAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367

Initial report from 04/16/2014 07:04:32

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077
Phone/Fax: (800) 220-3675 / (856) 786-5974
<http://www.EMSL.com> cinnaslab@EMSL.com

EMSL Order: 041410025
CustomerID: ENVI54
CustomerPO:
ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
0408BH14A 041410025-0031	MAIN FLOOR MASTER BATH - CERAMIC TILE	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH14B 041410025-0032	MAIN FLOOR MASTER BATH - CERAMIC TILE	White/Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH15A 041410025-0033	MAIN FLOOR MASTER BATH - CERAMIC TILE GROUT	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH15B 041410025-0034	MAIN FLOOR MASTER BATH - CERAMIC TILE GROUT	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH16A 041410025-0035	MAIN FLOOR MASTER BATH - CERAMIC TILE GLUE	Yellow Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH16B 041410025-0036	MAIN FLOOR MASTER BATH - CERAMIC TILE GLUE	Tan Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH17A 041410025-0037	2ND FLOOR KITCHEN - SELF- STICK LINOLEUM FLOOR TILE	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected

Analyst(s)

Brett Poulton (31)
Chelsey Bilhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-liable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%.

Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367

Initial report from 04/16/2014 07:04:32

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077
Phone/Fax: (800) 220-3675 / (856) 788-5974
<http://www.EMSL.com> cinnaslab@EMSL.com

EMSL Order: 041410025
CustomerID: ENVI54
CustomerPO:
ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
0408BH17B 041410025-0038	2ND FLOOR KITCHEN - SELF- STICK LINOLEUM FLOOR TILE	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH18A 041410025-0039	2ND FLOOR LAUNDRY - GREY TOP LAYER SELF- STICK FLOOR TILE	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH18B 041410025-0040	2ND FLOOR LAUNDRY - GREY TOP LAYER SELF- STICK FLOOR TILE	White Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH19A 041410025-0041	2ND FLOOR LAUNDRY - BOTTOM LAYER TAN SHEET FLOORING	Tan Fibrous Homogeneous		90% Non-fibrous (other)	10% Chrysotile
0408BH19B 041410025-0042	2ND FLOOR LAUNDRY - BOTTOM LAYER TAN SHEET FLOORING				Stop Positive (Not Analyzed)

Analyst(s)

Brett Poulton (31)
Chelsey Bilhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%
Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367

Initial report from 04/16/2014 07:04:32

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (800) 220-3675 / (856) 786-5974

<http://www.EMSL.com> cinnaslab@EMSL.com

EMSL Order: 041410025

CustomerID: ENVI54

CustomerPO:

ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos	
			% Fibrous	% Non-Fibrous	% Type	
0408BH20A 041410025-0043	EXTERIOR OF BUILDING - EXTERIOR WINDOW GLAZING COMPOUNDS	Tan/White Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected
0408BH20B 041410025-0044	EXTERIOR OF BUILDING - EXTERIOR WINDOW GLAZING COMPOUNDS	Tan/White Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected
0408BH20C 041410025-0045	EXTERIOR OF BUILDING - EXTERIOR WINDOW GLAZING COMPOUNDS	Tan/White Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected
0408BH21A 041410025-0046	EXTERIOR OF BUILDING - PAPER VAPOR BARRIER BEHIND SIDING	Brown Fibrous Homogeneous	90% Cellulose	10% Non-fibrous (other)		None Detected
0408BH21B 041410025-0047	EXTERIOR OF BUILDING - PAPER VAPOR BARRIER BEHIND SIDING	Brown Fibrous Homogeneous	95% Cellulose	5% Non-fibrous (other)		None Detected

Analyst(s)

Brett Poulton (31)
Chelsey Bilhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%
Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03038, PA ID# 68-00367

Initial report from 04/16/2014 07:04:32

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077
Phone/Fax: (800) 220-3675 / (856) 788-5974
<http://www.EMSL.com> cinnaslab@EMSL.com

EMSL Order: 041410025
CustomerID: ENVI54
CustomerPO:
ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos	
			% Fibrous	% Non-Fibrous	% Type	
0408BH22A 041410025-0048	EXTERIOR ROOF - TOP LAYER ROOF SHINGLE	Black Fibrous Homogeneous	20% Glass	80% Non-fibrous (other)		None Detected
0408BH22B 041410025-0049	EXTERIOR ROOF - TOP LAYER ROOF SHINGLE	Black Fibrous Homogeneous	20% Glass	80% Non-fibrous (other)		None Detected
0408BH23A 041410025-0050	EXTERIOR ROOF - BOTTOM LAYER ROOF SHINGLE	Black Fibrous Homogeneous	25% Cellulose	75% Non-fibrous (other)		None Detected
0408BH23B 041410025-0051	EXTERIOR ROOF - BOTTOM LAYER ROOF SHINGLE	Black Fibrous Homogeneous	20% Cellulose	80% Non-fibrous (other)		None Detected
0408BH24A 041410025-0052	EXTERIOR GARAGE - EXTERIOR WINDOW GLAZING COMPOUNDS	Tan Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected
0408BH24B 041410025-0053	EXTERIOR GARAGE - EXTERIOR WINDOW GLAZING COMPOUNDS	Tan Non-Fibrous Homogeneous		100% Non-fibrous (other)		None Detected

Analyst(s)

Brett Poulton (31)
Chelsey Bilhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%
Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00387

Initial report from 04/16/2014 07:04:32

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077
Phone/Fax: (800) 220-3675 / (856) 786-5974
<http://www.EMSL.com> cinnaaslab@EMSL.com

EMSL Order: 041410025
CustomerID: ENVI54
CustomerPO:
ProjectID:

Attn: **Kevin McCarthy**
Fuss & O'Neill EnviroScience, LLC
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 04/15/14 10:15 AM
Analysis Date: 4/15/2014
Collected:

Project: 20140277.A3E / 35 Old Dam Road, Fairfield, CT

Test Report: Asbestos Analysis of Bulk Materials via EPA 600/R-93/116 Method using Polarized Light Microscopy

Sample	Description	Appearance	Non-Asbestos		Asbestos
			% Fibrous	% Non-Fibrous	% Type
0408BH24C 041410025-0054	EXTERIOR GARAGE - EXTERIOR WINDOW GLAZING COMPOUNDS	Tan Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH25A 041410025-0055	EXTERIOR GARAGE - CONCRETE BLOCK	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH25B 041410025-0056	EXTERIOR GARAGE - CONCRETE BLOCK	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH26A 041410025-0057	EXTERIOR GARAGE - CONCRETE BLOCK GROUT	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected
0408BH26B 041410025-0058	EXTERIOR GARAGE - CONCRETE BLOCK GROUT	Gray Non-Fibrous Homogeneous		100% Non-fibrous (other)	None Detected

Analyst(s)

Brett Poulton (31)
Chelsey Bilhear (26)

Stephen Siegel, CIH, Laboratory Manager
or other approved signatory

EMSL maintains liability limited to cost of analysis. This report relates only to the samples reported and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities or analytical method limitations. Interpretation and use of test results are the responsibility of the client. This report must not be used by the client to claim product certification, approval, or endorsement by NVLAP, NIST or any agency of the federal government. Non-friable organically bound materials present a problem matrix and therefore EMSL recommends gravimetric reduction prior to analysis. Samples received in good condition unless otherwise noted. Estimated accuracy, precision and uncertainty data available upon request. Unless requested by the client, building materials manufactured with multiple layers (i.e. linoleum, wallboard, etc.) are reported as a single sample. Reporting limit is 1%.

Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NVLAP Lab Code 101048-0, AIHA-LAP, LLC-IHLAP Lab 100194, NYS ELAP 10872, NJ DEP 03036, PA ID# 68-00367

Initial report from 04/16/2014 07:04:32

Appendix C

Lead Paint Testing Procedures and Equipment

Standard Operating Procedures HUD and State of Connecticut Lead-Based Paint Inspections

Testing Procedures and Equipment

The U. S. Department of Housing and Urban Development (HUD) "Guidelines for the Evaluation and Control of Lead Hazards in Housing, September 1997" were consulted for this lead evaluation. HUD has been the agency at the federal level with responsibility for the establishment of national lead-based paint standards for testing and abatement. The HUD document will be referenced as the Guidelines in this report. The State of Connecticut Department of Public Health's current lead regulations, Lead Poisoning Prevention and Control (19a-111-1 through 19a-111-11) were also consulted.

This lead evaluation was comprehensive. A comprehensive inspection means that representative painted surfaces were systematically evaluated on a room-by-room basis in accordance with the Guidelines and the State of Connecticut regulations.

Lead-based paint surfaces and components were identified by utilizing on-site x-ray fluorescence (XRF) instruments. EnviroScience Consultants, Inc. owns and utilizes Radiation Monitoring Device LPA-1s (RMD instruments) exclusively for lead-based paint testing. Each instrument is operated in accordance with state and federal and manufacturer standards on the use of the instruments. State and federal protocols provide, with the exception of wall surfaces, one reading with the instrument on a representative component in each room, i.e., baseboard, chair rail, etc., as sufficient to establish the lead paint classification of all the representatives of that component type in a room. In the case of walls, because of the large spatial areas involved and the variability in lead content in paint over such large areas, the federal and state governments want a reading on each wall surface in a room. Therefore, representative testing is not permitted for walls.

The federal government has developed Performance Characteristic Sheets (PCS) for the type of instrument cited above. Each instrument must be calibrated in accordance with these PCSs on a 1.0-milligram lead standard. Each of EnviroScience's instruments has one of these standards assigned to it. Some of the standards were purchased directly from the government and the others from the manufacturers of the instruments.

For the RMD in the standard reading mode on metal, a Substrate Equivalent Lead (SEL) concentration has to be determined. To determine the SEL, the paint is removed from the surface of the component to obtain a bare substrate reading. After removing the paint, the surface is wiped with a 5% trisodium phosphate solution (a heavy duty cleaner). All paint residue is collected and properly disposed. Once the paint and surrounding area are cleaned, the XRF is utilized to determine the SEL for each surface. The SEL values are subtracted from the XRF values to determine the Corrected Lead Concentration (CLC). The CLC is the lead content of the paint on the component tested.

The RMD instrument has federal government-determined positive and negative ranges for the definition of lead-based paint. XRF results are classified using either the threshold or the inconclusive range. For the threshold, results are classified as positive if they are greater than or equal to the threshold and negative if they are less than the threshold. There is no inconclusive

classification when using the threshold values associated with an RMD instrument. The ranges for the RMD instrument and their various operating modes are as follows:

Radiation Monitoring Device LPA Analyzer 1

30-Second Standard Mode Reading Description	Substrate	Threshold (mg/cm ²)
Results corrected for substrate bias on metal substrate only.	Brick	1.0
	Concrete	1.0
	Drywall	1.0
	Metal	0.9
	Plaster	1.0
	Wood	1.0

Quick Mode Reading Description	Substrate	Threshold (mg/cm ²)	Inconclusive Range (mg/cm ²)
Readings not corrected for substrate bias on any substrate.	Brick	1.0	None
	Concrete	1.0	None
	Drywall	1.0	None
	Metal	1.0	None
	Plaster	1.0	None
	Wood	1.0	None

Prior to the start of any testing, a sketch of the building is drawn, and side designations are given to help identify exactly where readings were taken. Drawings depicting the room-numbering scheme are located on the cover page(s) for the building(s) inspected. Each side of the building was labeled A, B, C, or D. The wall "A" side of the unit is generally the side of primary entrance into a dwelling, and this room is always Room 1. Areas in the units include rooms, hallways, and closets. Areas are numbered in a clockwise fashion as building construction allows. This allows the inspector to indicate which substrate surface was tested. The condition of the surface is described by a check mark in the appropriate column, under the heading "condition of surface" on the testing form.

When more than one surface type was present on a side, the component tested was indicated with a number. If two windows were present on a building side, they were numbered left to right. Closet shelves and shelf supports were numbered top to bottom.

It is understood that the room layouts presented in the report are in conformance with the conditions that exist at the time the testing is performed. EnviroScience avoids labeling a room solely by its current functional use (i.e., living room, bedroom, etc.) since this use can change over time. Similarly, room layouts can change dramatically as dwellings are renovated and additions are built, incorporating existing rooms, or existing interior walls are moved or eliminated altogether.

Lead Dust Wipe Sampling Protocol

Data Collection

- A. A description of the sample location is recorded.
- B. Surface type (floor, windowsill, window well) is noted.
- C. Surface area measurements are recorded.

Wipe Sampling Method

- A. The area to be wiped is identified and measured.
- B. A disposable glove is put on and the "ghost wipe" package is opened.
- C. Without touching any other surface, the wipe is opened and placed flat down on the surface. Using firm, consistent pressure, a wipe is taken in a single "S" motion.
- D. Next the wipe is folded in half with the contaminated side facing inward and another wipe is taken again at 90 degrees to the first "S" wipe. Do not use a scrubbing motion, but be sure to collect all visible dust in the measured area.
- E. The wipe is folded again with the contaminated side inward. Without touching any other surface, the wipe is placed into a plastic centrifuge tube. The tube is sealed and labeled. The sample number indicates the date and sampler's identity.
- F. The samples are submitted to our laboratory on our standard sample log. Date and time of transfer is recorded to ensure proper chain of custody. The analytical procedure utilized is a modified EPA SW-846-3050. Blanks are submitted in accordance with EnviroScience's QA/QC program.

Fuss and O'Neill EnviroScience, LLC

Lead In Soil Composite Sampling Protocol

Linear Transect Method:

For use around roadways, buildings, and other structures such as painted fencing, concrete walls, etc. Each side of the building is labeled with a letter. The 'A' side of the building is the street side. The remaining sides are labeled B, C, and D, clockwise around the building. Fencing and concrete walls are similarly labeled if there is a street side. Otherwise, along with roadways, these structures can be labeled using the directional points North, South, East and West.

1. Linear transects are established parallel to the building, wall, fence or roadway at 2 foot intervals.
2. Three (3) to ten (10) distinct locations roughly equidistant from one another along the transect line are selected as sample points. As a general rule, we would like to see five sampling points for each 100 feet of transect line, but sample points should be at least 2 feet apart, so in smaller areas (less than 10 feet), fewer samples may be collected.
3. Samples of the top one-half inch (.5") of soil should be taken using a metal spoon or stainless-steel scoop. Collect soil until a circular hole of approximately 2 inches in diameter (0.5" deep) has been created. Samples from each of the sampling points should be composited into a 24-ounce plastic bag of at least 3 mil in weight. The bags should be either zip-locked or foldable with puncture proof tabs.
4. After each composite sample is collected, the sampling spoon or scoop should be thoroughly cleaned with a disposable wipe to prevent cross contamination of other composite samples to be collected in other areas on the site.
5. The soil samples are dried, weighed out and digested in nitric acid according to EPA Method 3050. Analysis is performed by direct aspiration flame atomic absorption spectrophotometry according to EPA Method 7420. Results are expressed in milligrams per kilogram (mg/kg), or parts-per-million (ppm).

Grid Method:

In other areas, such as play areas and other open spaces, an X shaped axis should be developed with directional reference points of North, South, East and West. At least five, but not more than ten sampling points should be designated along each axis. The sampling points should be equidistant from one another and should be at least one foot distant from each other.

The sampling and compositing procedures outlined in the linear transect method should be followed for each axis.

For all soil sampling, a property sketch should be drawn. It is recommended that you use the space provided on the back of the lead in soil sample log.

Appendix D

Lead Testing Field Data Sheets



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

LEAD INSPECTION COVER SHEET

Inspector's Information

Inspector's Name: Robert Hobbins License Number: 2156
XRF Model: LPA - 1B Serial Number: 1377
Date of Inspection: April 8, 2014 Project Number: 20140277.A3E

Property Information

Building Address: 35 Old Dam Road
(Street)
Fairfield CT Age of Property: N/A
(City) (State)

Describe Structure:

Sheetrock ceilings and walls with wood / metal window and door systems and concrete and wood floors
Exterior wood siding and concrete foundation

Are there lead hazards present? ☐ Yes ☒ No
Were lead dust wipes taken? ☐ Yes ☒ No
Were soil samples collected? ☐ Yes ☒ No
Were drinking water samples collected? ☐ Yes ☒ No

Single Family Dwelling ☒

Is there an EBL child present?
☐ Yes ☒ No ☐ Unknown

Is there a child under six years of age in the dwelling?
☐ Yes ☒ No ☐ Unknown

Multiple Family Dwelling ☐

Number of units in building: _____
Number of units tested: _____
Is there an EBL child present in the building?
☐ Yes ☐ No ☐ Unknown
If EBL child, which unit(s)? _____
Is there a child under six years of age in the building?
☐ Yes ☐ No ☐ Unknown
If child under six, which unit(s)? _____

XRF Calibration Check

Calibration Paint Film Used: ☐ NIST 1.02 mg/cm² ☒ Manufacturer's Standard 1.0 mg/cm²
Calibration Check Limits Used: ☒ RMD (0.7 to 1.3 mg/cm² inclusive)
☐ Scitec MAP4 (0.6 to 1.2 mg/cm² inclusive)

	Hour	First Reading	Second Reading	Third Reading	Average
First Check	900	1.0	0.9	1.0	0.96
Second Check	1100	1.0	1.0	1.1	1.03
Third Check	1300	0.9	1.2	1.0	1.03
Fourth Check					



FUSS & O'NEILL

Prepared By

Date

Checked By

Date


Project No

MAIN FLOOR

Sheet No
of

OLD DFM ROAD

D



FRONT DOOR

A



FUSS & O'NEILL

Prepared By

Date


Checked By

Date

Project No

2ND FLOOR LOFT AREA

Sheet No
of



XRF FIELD DATA SHEET – INTERIOR ROOM

Address: 35 Old Dam Rd. Fairfield, CT

Apt. #: _____

Floor: 2nd

Room: CLOSET AS BATH

Page ____ of ____

Project Name: 35 Old Dam Rd.

Project Number: 20140277.A3E

Project Manager: K. McCarthy (If Positive - Check All That Apply) * Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B, N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

[illegible]

Notes:



146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

Address: 35 Old Dam Rd. Fairfield, CT

Apt. #: _____

Floor: Bottom Main

Room: Bedroom 3 closet

Page ____ of ____

Project Name: 35 Old Dam Rd.

Project Number: 20140277.A3E

Project Manager: K. McCarthy (If Positive - Check All That Apply) * Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B, N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes: _____



146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

Address: 35 Old Dam Rd, Fairfield, CT

Apt. #: _____

Floor: Main

Room: Pages closed

Page _____ of _____

Project Name: 35 Old Dam Rd.

Project Number: 20140277.A3E

Project Manager: K. McCarthy (If Positive - Check All That Apply) * Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B, N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes: _____



146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

Address: 35 Old Dam Rd, Fairfield, CT

Apt. #: _____

Floor: Main

Room: OFFICE CLOSING

Page ____ of ____

Project Name: 35 Old Dam Rd.

Project Number: 20140277.A3E

Project Manager: K. McCarthy (If Positive - Check All That Apply) * Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B, N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes:



146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET – INTERIOR ROOM

Address: 35 Old Dam Rd, Fairfield, CT

Apt. #: _____

Floor: 4th

Room: Bedroom 1 closet

Page _____ of _____

Project Name: 35 Old Dam Rd.

Project Number: 20140277.A3E

Project Manager: K. McCarthy (If Positive - Check All That Apply) * Substrate Type: Mctal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B, N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes:



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET – INTERIOR ROOM

Address: 35 Old Dam Road, Fairfield, CT

Apt. #: _____

Floor: 1st

Room: BDL 1

Page 1 of 13

Project Name: 35 Old Dam Road

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Floor								
	Baseboards	-0.1		W					
A	Wall	-0.0		SR					
B	Wall	-0.0		SR					
C	Wall	0.1		SR					
D	Wall	-0.1		SR					
	Chair rail								
	Ceiling	0.0		SR					
	Crown Molding								
	Door								
	Casing								
	Jamb								
	Door	-0.0		W					
	Casing	0.0		W					
	Jamb	-0.0		W					
	Window Trim	-0.1		W					
	Sill	0.2		W					
	Sash	0.1		W					
	Well								
	Cabinet Base								
	Door Exterior								
	Door Interior								
	Walls								
	Shelves								
	Shelf Supports								
	Closet Shelf								
	Shelf Supports								
	Radiator	-0.0		M					
	Wall Molding								

* Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B

N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes: _____



146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

Address: 35 Old Dam Road, Fairfield, CT

Apt. #: _____

Floor: 1st Floor

Room: BATA 1

Page 2 of 13

Project Name: 35 Old Dam Road

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

* Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B

N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes:

Wall	-	-0.0	SE	Dowl	-0.0	Ceiling	-0.1	SR
Wall	-	-0.1	↓	DJ	0.0			
Wall	-	0.0		DJ	-0.0			
Wall	-	-0.0						



XRF FIELD DATA SHEET - INTERIOR ROOM

Address: 35 Old Dam Road, Fairfield, CT

Apt. #: _____

Floor: 1st Room: Office

Page 3 of 13

Project Name: 35 Old Dam Road Project Number: 20140277.A3E

Project Manager: K. McCarthy (If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Floor								
	Baseboards	0.1		W					
A	Wall	-0.0		SR					
B	Wall	0.0		I					
C	Wall	-0.1		I					
D	Wall	0.0		I					
	Chair rail								
	Ceiling	0.0		SR					
	Crown Molding								
	Door	0.0		W					
	Casing	0.1		W					
	Jamb	0.1		W					
	Door								
	Casing								
	Jamb								
	Window Trim	-0.1		W					
	Sill	0.1		W					
	Sash	-0.0		W					
	Well								
	Cabinet Base								
	Door Exterior								
	Door Interior								
	Walls								
	Shelves								
	Shelf Supports								
	Closet Shelf								
	Shelf Supports								
	Radiator								
	Wall Molding								

* Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B

N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes: _____



XRF FIELD DATA SHEET – INTERIOR ROOM

Address: 35 Old Dam Road, Fairfield, CT

Apt. #: _____

Floor: PT

Room: BR 2

Page 4 of 13

Project Name: 35 Old Dam Road

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Floor								
	Baseboards	-0.2		W					
A	Wall	0.0		SR					
B	Wall	-0.0		SR					
C	Wall	0.1		SR					
D	Wall	-0.0		SR					
	Chair rail								
	Ceiling	-0.2		SR					
	Crown Molding								
	Door	0.0		W					
	Casing	-0.1		W					
	Jamb	0.1		W					
	Door								
	Casing								
	Jamb								
	Window Trim	-0.1		W					
	Sill	-0.0		W					
	Sash	0.1		W					
	Well								
	Cabinet Base								
	Door Exterior								
	Door Interior								
	Walls								
	Shelves								
	Shelf Supports								
	Closet Shelf								
	Shelf Supports								
	Radiator	0.7		M					
	Wall Molding								

* Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B

N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes: _____



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET - INTERIOR ROOM

Address: 35 Old Dam Road, Fairfield, CT

Apt. #: _____

Floor: 1ST

Room: BR 3

Page 5 of 13

Project Name: 35 Old Dam Road

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Floor								
	Baseboards	0.0		W					
A	Wall	~0.1		SR					
B	Wall	-0.0		SR					
C	Wall	0.1		SR					
D	Wall	-0.0		SR					
	Chair rail								
	Ceiling	0.0		SR					
	Crown Molding								
	Door	0.0		W					
	Casing	0.1		W					
	Jamb	0.0		W					
	Door								
	Casing								
	Jamb								
	Window Trim	0.1		W					
	Sill	0.1		W					
	Sash	0.0		W					
	Well	-0.0		W					
	Cabinet Base								
	Door Exterior								
	Door Interior								
	Walls								
	Shelves								
	Shelf Supports								
	Closet Shelf								
	Shelf Supports								
	Radiator	-0.2		W					
	Wall Molding								

* Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B
N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes: _____



146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET – INTERIOR ROOM

Address: 35 Old Dam Road, Fairfield, CT

Apt. #: _____

Floor: 2nd Floor Room: Kitchen

Page 6 of 13

Project Name: 35 Old Dam Road Project Number: 20140277.A3E

Project Manager: K. McCarthy (If Positive - Check All That Apply)

* Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B
N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement
Notes: _____



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET - INTERIOR ROOM

Address: 35 Old Dam Road, Fairfield, CT

Apt. #: _____

Floor: 2nd

Room: BATH 3

Page 7 of 13

Project Name: 35 Old Dam Road

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Floor								
	Baseboards	-0.2		W					
A	Wall	0.1		SR					
B	Wall	-0.1		SR					
C	Wall	-0.1		SR					
D	Wall	-0.0		SR					
	Chair rail								
	Ceiling	0.1		SR					
	Crown Molding								
	Door								
	Casing								
	Jamb								
	Door	0.0		W					
	Casing	0.1		W					
	Jamb	0.2		W					
	Window Trim	0.1		W					
	Sill	0.1		W					
	Sash	-0.0		W					
	Well								
	Cabinet Base								
	Door Exterior								
	Door Interior								
	Walls								
	Shelves								
	Shelf Supports								
	Closet Shelf								
	Shelf Supports								
	Radiator	0.2		M					
	Wall Molding								

* Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B

N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes: _____



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET - INTERIOR ROOM

Address: 35 Old Dam Road, Fairfield, CT

Apt. #: _____

Floor: 2nd

Room: LOFT

Page 8 of 13

Project Name: 35 Old Dam Road

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Floor								
	Baseboards	-0.1		W					
A	Wall	-0.1		SR					
B	Wall	0.0		SR					
C	Wall	-0.1		SR					
D	Wall	-0.0		SR					
	Chair rail								
	Ceiling	-0.1		SR					
	Crown Molding								
	Door	0.1		W					
	Casing	0.0		W					
	Jamb	-0.1		W					
	Door								
	Casing								
	Jamb								
	Window Trim	0.0		W					
	Sill	0.1		W					
	Sash	NP							
	Well								
	Cabinet Base								
	Door Exterior								
	Door Interior								
	Walls								
	Shelves								
	Shelf Supports								
	Closet Shelf								
	Shelf Supports								
	Radiator	0.1		M					
	Wall Molding								

* Substrate Type: Metal = M, Wood = W, Plaster = P, Sheetrock = S, Concrete = C, Brick = B

N/A = Not Accessible; N/C = Not Coated; COV = Covered; VR = Vinyl Replacement

Notes: _____



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET - EXTERIOR OF SIDE

Address: 35 Old Dam Rd, Fairfield, CT

Page 9 of 13

Project Name: 35 Old Dam Rd, Fairfield,

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Foundation								<i>Garage - Annex</i>
	Skirt Board								
	Corner Boards								
	Siding	<i>79.9</i>	<i>/</i>	<i>W</i>	<i>NBS</i>				<i>interior siding</i>
	Upper Trim								
	Door	<i>0.1</i>		<i>W</i>					
	Casing	<i>0.1</i>		<i>W</i>					
	Jamb	<i>0.2</i>		<i>W</i>					
	Threshold								
	Kick Board								
	Storm Door								
	Window Sill								
	Trim								
	Sash								
	Blind Stops								
	Storm Window								
	Basement Sash								
	Frame								
	Bulkhead								
	Downspouts								
	Porch Floor								
	Ceiling Joist								
	Lower Trim								
	Lower Railing								
	Balusters								
	Railing Cap								
	Ceiling								
	Lattice								
	Lattice Frame								
	Support Columns								
	Column Base								
	Brackets								
	Hand Rails								
	Treads								
	Risers								
	Stringers								

Ext. Siding

0.1

W



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET - EXTERIOR OF SIDE A

Address: 35 Old Dam Road, Fairfield, CT

Page 10 of 13

Project Name: 35 Old Dam Road

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Foundation								
	Skirt Board								
	Corner Boards								
	Siding	0.2		W					
	Upper Trim								
	Door	0.1		W					
	Casing	0.0		W					
	Jamb	0.1		W					
	Threshold								
	Kick Board								
	Storm Door								
	Window Sill	0.1		W					
	Trim	0.0		W					
	Sash	0.0		W					
	Blind Stops								
	Storm Window								
	Basement Sash								
	Frame								
	Bulkhead								
	Downspouts								
	Porch Floor								
	Ceiling Joist								
	Lower Trim								
	Lower Railing								
	Balusters								
	Railing Cap								
	Ceiling								
	Lattice								
	Lattice Frame								
	Support Columns								
	Column Base								
	Brackets								
	Hand Rails								
	Treads								
	Risers								
	Stringers								



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET - EXTERIOR OF SIDE B

Address: 35 Old Dam Road, Fairfield, CT

Page 11 of 13

Project Name: 35 Old Dam Road

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Foundation								
	Skirt Board								
	Corner Boards								
	Siding	0.1		W					
	Upper Trim								
	Door	0.0		W					
	Casing	0.0		W					
	Jamb	-0.1		W					
	Threshold								
	Kick Board								
	Storm Door								
	Window Sill	0.1		W					
	Trim	-0.1		W					
	Sash	0.0		W					
	Blind Stops								
	Storm Window								
	Basement Sash								
	Frame								
	Bulkhead								
	Downspouts								
	Porch Floor								
	Ceiling Joist								
	Lower Trim								
	Lower Railing								
	Balusters								
	Railing Cap								
	Ceiling								
	Lattice								
	Lattice Frame								
	Support Columns								
	Column Base								
	Brackets								
	Hand Rails								
	Treads								
	Risers								
	Stringers								



FUSS & O'NEILL
EnviroScience, LLC

www.fando.com

146 Hartford Road, Manchester, CT 06040

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET - EXTERIOR OF SIDE C

Address: 35 Old Dam Rd, Fairfield, CT

Page 12 of 13

Project Name: 35 Old Dam Rd, Fairfield,

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Foundation								
	Skirt Board								
	Corner Boards								
	Siding	0.3		W					
	Upper Trim								
	Door								
	Casing								
	Jamb								
	Threshold								
	Kick Board								
	Storm Door								
	Window Sill	0.2		W					
	Trim	0.7		W					
	Sash	1.1	✓	W	NO				
	Blind Sash Shutter	0.3		W					
	Storm Window								
	Basement Sash								
	Frame								
	Bulkhead	0.2		M					
	Downspouts								
	Porch Floor								
	Ceiling Joist								
	Lower Trim								
	Lower Railing								
	Balusters								
	Railing Cap								
	Ceiling								
	Lattice								
	Lattice Frame								
	Support Columns								
	Column Base								
	Brackets								
	Hand Rails								
	Treads								
	Risers								
	Stringers								



FUSS & O'NEILL
EnviroScience, LLC

146 Hartford Road, Manchester, CT 06040

www.fando.com

(860) 646-2469 Fax (860) 649-6883

XRF FIELD DATA SHEET - EXTERIOR OF SIDE D

Address: 35 Old Dam Rd, Fairfield, CT

Page 13 of 13

Project Name: 35 Old Dam Rd, Fairfield,

Project Number: 20140277.A3E

Project Manager: K. McCarthy

(If Positive - Check All That Apply)

Side	Surface	XRF Readings	POS	Substrate	Defective	Chewable	Friction	Impact	Comments
	Foundation								
	Skirt Board								
	Corner Boards								
	Siding	0.0		W					
	Upper Trim								
	Door								
	Casing	0.2		W					
	Jamb								
	Threshold								
	Kick Board								
	Storm Door								
	Window Sill								
	Trim								
	Sash								
	Blind Stops								
	Storm Window								
	Basement Sash								
	Frame								
	Bulkhead								
	Downspouts								
	Porch Floor								
	Ceiling Joist								
	Lower Trim								
	Lower Railing								
	Balusters								
	Railing Cap								
	Ceiling								
	Lattice								
	Lattice Frame								
	Support Columns								
	Column Base								
	Brackets								
	Hand Rails								
	Treads								
	Risers								
	Stringers								

Appendix E

Lead in Dust Wipe Sample Results and Chain of Custody Form

FUSS & O'NEILL EnviroScience, LLC

146 Hartford Road, Manchester, CT 06040

201406857

www.fusdo.com

(860) 646-2469 Fax (860) 649-6883

SAMPLE LOG FOR LEAD WIPES

Sheet No. 1 of 1

Project Name: Lot 100 Assoc.
Building: 35 Old Farm Rd

Project Number: 201406857-ASC
Project Manager: Rua

Sample ID Number	Sample Location/Building	Surface Element	Area Sq. Ft.	Result (ug/ft)	Lab Number
1-05070114-03	Room #2	Floor	144		
2-04	Room #2 C-Window	W. Sill	36		
3-05	Room #4	Floor	144		
4-06	Room #4 - Dup	Floor	144		
5-07	Room #4 - Window	W. Sill	36		
6-08	Room #4 - Window	W. Sill	36		
7-09	Room #6	Floor	144		
8-10	Room #9 - 2 Window	W. Sill	36		
9-11	Room #9	Floor	144		
10-12	Blank	N/A	—		
11-13	Blank	N/A	—		

Analysis Method: EPA SW-846-3050(MOD.)

Wipe Media

☒ ASTM

☐ Non ASTM

Turnaround Time 24 hrs

Based on the turnaround time indicated above, analyses are due at Fuss & O'Neill EnviroScience on or before this date: 5/10/14
Please call the Fuss & O'Neill EnviroScience laboratory at 860-646-2469 if analyses will be late.

Fax Results To: Fuss & O'Neill EnviroScience Laboratory at 888-838-1160

Special Instructions:

Sample Collected By: Mike August Date: 5/7/14 Time: 10:20
Sample Rec'd/Scnt By: Ben Date: 5/8/14 Time: 10:25am EMSL
Sample Received By: Ben Date: 5/8/14 Time: 10:25am EMSL

Shipped To: ☒ EMSL (State) NJ ☐ Other

Method of Shipment: ☒ Fed Ex ☐ UPS Overnight ☐ UPS Ground ☐ Other

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (856) 303-2500 / (856) 786-5974

<http://www.EMSL.com>cinnaminsonleadlab@emsl.com

EMSL Order: 2Q1406857
 CustomerID: ENV154
 CustomerPO: 20140277.A3E
 ProjectID:

Attn: **Fuss & O'Neill EnviroScience, LLC**
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
 Fax: (888) 838-1160
 Received: 05/08/14 10:23 AM
 Collected: 5/7/2014

Project: 20140277.A3E / Lothrop Assoc. / 35 Old Dorm Road Fairfield, CT

Test Report: Lead in Dust by Flame AAS (SW 846 3050B/7000B)*

Client Sample Description	Lab ID	Collected	Analyzed	Area Sampled	Lead Concentration
050714UA-03	0001	5/7/2014	5/9/2014	144 in ²	<10 µg/ft ²
Site: Room #2 Floor					
050714UA-04	0002	5/7/2014	5/9/2014	36 in ²	<40 µg/ft ²
Site: Room #2 C-Window W.Sill					
050714UA-05	0003	5/7/2014	5/9/2014	144 in ²	<10 µg/ft ²
Site: Room #4 Floor					
050714UA-06	0004	5/7/2014	5/9/2014	144 in ²	46 µg/ft ²
Site: Room #4 Dup Floor					
050714UA-07	0005	5/7/2014	5/9/2014	36 in ²	370 µg/ft ²
Site: Room #4- Window W.Sill					
050714UA-08	0006	5/7/2014	5/9/2014	36 in ²	<40 µg/ft ²
Site: Room #8 D- Window W.Sill					
050714UA-09	0007	5/7/2014	5/9/2014	144 in ²	<10 µg/ft ²
Site: Room #8 Floor					
050714UA-10	0008	5/7/2014	5/9/2014	36 in ²	<40 µg/ft ²
Site: Room #9- D2 Window W.Sill					
050714UA-11	0009	5/7/2014	5/9/2014	144 in ²	<10 µg/ft ²
Site: Room #9 Floor					
050714UA-12	0010	5/7/2014	5/9/2014	n/a	<10 µg/wipe
Site: Blank					
050714UA-13	0011	5/7/2014	5/9/2014	n/a	<10 µg/wipe
Site: Blank					

Julie Smith - Laboratory Director
 NJ-NELAP Accredited:03036
 or other approved signatory

*Analysis following Lead in Dust by EMSL SOP/Determination of Environmental Lead by FLAA. Reporting limit is 10 µg/wipe. µg/wipe = µg/ft² x area sampled in ft². Unless noted, results in this report are not blank corrected. This report relates only to the samples reported above and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities (such as volume sampled) or analytical method limitations. Samples received in good condition unless otherwise noted. The lab is not responsible for data reported in µg/ft² which is dependent on the area provided by non-lab personnel. The test results contained within this report meet the requirements of NELAP unless otherwise noted. "<" (less than) results signifies that the analyte was not detected at or above the reporting limit. Measurement of uncertainty is available upon request. The QC data associated with the sample results included in this report meet the recovery and precision requirements established by the AIHA-LAP, unless specifically indicated otherwise.

Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NELAP Certifications: NJ 03036, NY 10872, PA 68-00367, AIHA-LAP, LLC ELLAP 100194, AZLA 2845.01

Initial report from 05/09/2014 11:18:16

Appendix F

Lead in Soil Sample Results and Chain of Custody Form

10

SAMPLE LOG FOR LEAD SOIL

Sheet No. 1 of 1

Project Name: Lothrop Assoc.
Building: 35 old Barn Rd Fairfield, CT

Project Number: 20140277-ABC
Project Manager: KM

[illegible]

Analysis Method: EPA-SW-846-3050-7420

Turnaround Time 24 hrs

Date: _____ Time: _____
Date: _____ Time: _____

Based on the turnaround time indicated above, analyses are due to Fuss & O'Neill EnviroScience on or before this date: 5/10/14
Please call the Fuss & O'Neill EnviroScience laboratory at 860-646-2469 if analyses will be late.

Fax Results To: Fuss & O'Neill EnviroScience Laboratory at 888-838-1160

Special Instructions:

Samples Collected By: William August Date: 5/7/14 Time: 1038
 Samples Rec'd/Sent By: _____ Date: _____ Time: _____
 Samples Received By: Paula Date: 5/8/14 Time: 10:23am EMSL-FX

Shipped To: ☒ EMSL (State) GA ☐ Other _____

Method of Shipment: ☒ Fed Ex ☐ UPS Overnight ☐ UPS Ground ☐ Other _____

(SEE REVERSE FOR DIAGRAM)

**EMSL Analytical, Inc.**

200 Route 130 North, Cinnaminson, NJ 08077

Phone/Fax: (856) 303-2500 / (856) 788-5974

<http://www.EMSL.com>cinnaminsonleadlab@emsl.com

EMSL Order: 201406826
CustomerID: ENVI54
CustomerPO: 20140277.A3E
ProjectID:

Attn: **Fuss & O'Neill EnviroScience, LLC**
146 Hartford Road
Manchester, CT 06040

Phone: (860) 646-2469
Fax: (888) 838-1160
Received: 05/08/14 10:23 AM
Collected: 5/7/2014

Project: 20140277.A3E / Lothrop Assoc. / 35 Old Dom Road Fairfield, CT

Test Report: Lead in Soils by Flame AAS (SW 846 3050B/7000B)*

Client Sample Description	Lab ID	Collected	Analyzed	Lead Concentration
050714UA-14	0001	5/7/2014	5/8/2014	740 mg/Kg
Site: A-Side @ Dripline Desc: Bare				
050714UA-15	0002	5/7/2014	5/8/2014	66 mg/Kg
Site: C-Side @ Dripline Desc: Bare				
050714UA-16	0003	5/7/2014	5/8/2014	160 mg/Kg
Site: D-Side @ Dripline Desc: Bare				

Julie Smith - Laboratory Director
NJ-NELAP Accredited: 03036
or other approved signatory

*Analysis following Lead in Soil/Solids by EMSL SOP/Determination of Environmental Lead by FLAA. Reporting limit is 40 mg/kg based on the minimum sample weight per our SOP. Unless noted, results in this report are not blank corrected. This report relates only to the samples reported above and may not be reproduced, except in full, without written approval by EMSL. EMSL bears no responsibility for sample collection activities. Samples received in good condition unless otherwise noted. Results reported based on dry weight. "<" (less than) result signifies that the analyte was not detected at or above the reporting limit. Measurement of uncertainty is available upon request. The QC data associated with the sample results included in this report meet the recovery and precision requirements established by the AIA-LAP, unless specifically indicated otherwise.

Samples analyzed by EMSL Analytical, Inc. Cinnaminson, NJ NELAP Certifications: NJ 03036, NY 10872, PA 68-00367, AIA-LAP, LLC ELLAP 100194, A2LA 2845.01

Initial report from 05/08/2014 20:43:34

Appendix G

Lead in Drinking Water Sample Results and Chain of Custody Form

Page 1

Date Samples Received: 05/07/14

Client Name : Fuss & O'Neill EnviroScience
Report Date : 05/09/14

CTL Lab No. : 0514109
PO/ Job No. : 20140277.A3E

RESULTS OF ANALYSIS**EPA Method 200.9**

Matrix Type :	W	W
CTL Sample No.:	0218	0219
Field ID :	1 st Draw	Flush
	Kitchen Sink	Kitchen Sink
	050714UA-01	050714UA-02

Parameters	RL			Date Analyzed
Total Lead-mg/L	0.005	0.129	0.008	05/08/14

RL= Reporting Limit ND= Not Detected

Matrix Type: W= Water/Aqueous S= Sol/Solid O= Oil/Hydrocarbon

Appendix H

Airborne Radon Gas Assessment Results and Chain of Custody Form



FUSS & O'NEILL
EnviroScience, LLC

4/11/14
ENVIII
DE

Radon Testing Summary Sheet

Contact/Phone #: Kevin McCarthy/203-374-3748 x3533

Placed by: B. Hobbins

Project #: 20140277.A3E

Retrieved by: J Blum

Building: 35 Old Dam Road

Start Date: 4-8-14

Address: 35 Old Dam Road

Stop Date: 4-10-14

Fairfield, CT 06824-

Weather at Placement: Rain, 45°

email results to kmccarthy@fando.com ✓

Instructions: Tear off center bar coded label from canister and affix to sheet in spaces provided. Please make sure top bar coded label is left on detector. Identify test location for each detector in space as necessary. Please

REMOVE THIS PORTION AND AFFIX TO TEST INFORMATION FORM 2299423

REMOVE THIS PORTION AND KEEP FOR YOUR RECORDS 2299423

Client

REMOVE THIS PORTION AND AFFIX TO TEST INFORMATION FORM 2314120

REMOVE THIS PORTION AND KEEP FOR YOUR RECORDS 2314120

Client

RADON TESTING CORP. OF AMERICA

detector (room #, location in room) or if detector is missing or damaged

Start Time: 10:30
Stop Time: 10:30
Identifier: _____

BDR 2

Start Time: 10:32
Stop Time: 12:32
Identifier: _____

OFFICE

Start Time: _____
Stop Time: _____
Identifier: _____

Start Time: _____
Stop Time: _____
Identifier: _____

Start Time: _____
Stop Time: _____
Identifier: _____

REMOVE THIS PORTION AND AFFIX TO TEST INFORMATION FORM 2313946

REMOVE THIS PORTION AND KEEP FOR YOUR RECORDS 2313946

Client

REMOVE THIS PORTION AND AFFIX TO TEST INFORMATION FORM 2314000

REMOVE THIS PORTION AND KEEP FOR YOUR RECORDS 2314000

Client

RADON TESTING CORP. OF AMERICA

Start Time: 10:30
Stop Time: 10:30
Identifier: _____

BDR 2 - D

Start Time: _____
Stop Time: _____
Identifier: _____

OFFICE - B

Start Time: _____
Stop Time: _____
Identifier: _____

Start Time: _____
Stop Time: _____
Identifier: _____

Start Time: _____
Stop Time: _____
Identifier: _____

56 Quarry Road, Trumbull, CT 06611
t (203) 374-3748
f (203) 374-4391
www.FandO.com

Connecticut
Massachusetts
New York
Rhode Island
South Carolina

Site Radon Inspection Report

Date : 4/11/2014

Ms. Karron Redfield
Fuss & O'Neill Enviroscience, LLC
146 Hartford Road
Manchester, CT 06040-

Client: Project #: 20140277.A3E
Test Location 35 Old Dam Road

Fairfield, CT 06824-

Individual Canister Results

Canister ID# : 2299423
Canister Type : Charcoal Canister 3 inch
Location : Bdrm 2
Radon Level : **0.5 pCi/L**
Error for Measurement is: \pm 0.2 pCi/L

Test Start : 04/08/2014 @ 10:30
Test Stop : 04/10/2014 @ 10:30
Received: 04/11/2014 @ 10:39
Analyzed: 04/11/2014 @ 14:51

Canister ID# : 2313946
Canister Type : Charcoal Canister 3 inch
Location : Bdrm 2 - D
Radon Level : **0.4 pCi/L**
Error for Measurement is: \pm 0.2 pCi/L

Test Start : 04/08/2014 @ 10:30
Test Stop : 04/10/2014 @ 10:30
Received: 04/11/2014 @ 10:39
Analyzed: 04/11/2014 @ 14:51

Canister ID# : 2314000
Canister Type : Charcoal Canister 3 inch
Location : Office - B
Radon Level : **0.4 pCi/L**
Error for Measurement is: \pm 0.2 pCi/L

Test Start : 04/08/2014 @ 10:32
Test Stop : 04/10/2014 @ 10:32
Received: 04/11/2014 @ 10:39
Analyzed: 04/11/2014 @ 14:51

Canister ID# : 2314120
Canister Type : Charcoal Canister 3 inch
Location : Office
Radon Level : **0.2 pCi/L**
Error for Measurement is: \pm 0.2 pCi/L

Test Start : 04/08/2014 @ 10:32
Test Stop : 04/10/2014 @ 10:32
Received: 04/11/2014 @ 10:39
Analyzed: 04/11/2014 @ 14:51



Andreas C. George
Andreas C. George
Radon Measurement Specialist
NJ MES 11089

Dante Galan
Dante Galan
Laboratory Director

NRSB ARL0001
NYS ELAP ID: 10806
PADEP ID: 0346
NJDEP ID: NY933
NJ MEB 90036
FL DOH RB1609

Site Radon Inspection Report

Date : 4/11/2014

The reported results indicate that radon levels in the building tested are below the United States Environmental Protection Agency (EPA) action level of 4.0 picoCuries per liter of air (pCi/L). The EPA recommends retesting if your living patterns change and you begin occupying a lower level of the building, such as a basement or if major remodeling is done.

General radon information may be obtained by consulting the EPA booklet: A Citizen's Guide to Radon (www.epa.gov/radon/pubs/ditguide.html). To request a copy or for further information, please contact your state health department. The EPA maintains a radon information website, including copies of its publications, at www.epa.gov/iaq/radon.

For New Jersey clients: Please see the attached guidance document entitled Radon Testing and Mitigation: The Basics for further information.

For New York clients: If the radon level of one or more testing devices is equal to or exceeds 20 pCi/L please contact the New York State Department of Health, Bureau of Environmental Radiation Protection, for technical advice and assistance at 518-402-7556 or toll free 1-800-458-1158.

PLEDGE OF ASSURED QUALITY

All procedures used for generating this report are in complete accordance with the current EPA protocols for the analysis of radon in air (EPA 402-R-92-004). The analytical results relate only to the samples tested, in the condition received by the lab, and that calculations were based upon the information supplied by client. RTCA and its personnel do not assume responsibility or liability, collectively and individually, for analysis results when detectors have been improperly handled or placed by the consumer, nor does RTCA and its personnel accept responsibility for any financial or health consequences of subsequent action or lack of action, taken by the customer or its consultants based on RTCA-provided results.




Andreas C. George
Radon Measurement Specialist
NJ MES 11089

Dante Galan
Laboratory Director

NRSB ARL0001
NYS ELAP ID: 10806
PADEP ID: 0346
NJDEP ID: NY933
NJ MEB 90036
FL DOH RB1609

JOINS PANEL 0419



MAP SCALE 1" = 500'



NATIONAL FLOOD INSURANCE PROGRAM

PANEL 0557G

FIRM

FLOOD INSURANCE RATE MAP
FAIRFIELD COUNTY,
CONNECTICUT
(ALL JURISDICTIONS)

PANEL 557 OF 626

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS
COMMUNITY
FAIRFIELD COUNTY, CT
LUMBER
SUFFICIENT
G

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.



MAP NUMBER
09001C0557G
MAP REVISED
JULY 8, 2013

Federal Emergency Management Agency

This is an official copy of a portion of the above referenced flood map. It was extracted using F-MIT On-Line. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For the latest product information about National Flood Insurance Program flood maps check the FEMA Flood Map Store at www.msc.fema.gov

Zoning Information -- Zone "A" Residential

STATUS	ITEM	REQUIRED	EXISTING CONDITION	PROPOSED	AS-BUILT CONDITION
	MINIMUM LOT AREA	9,315 S.F.			9,361 S.F.
	MIN. SQUARE ON LOT	7%	6%		
	MINIMUM LOT FRONTAGE	20'	40'		40'
	MINIMUM LOT FRONTAGE PER THE DISTRICTS ZONING ORDINANCE				
	ONE PARK V	9,315 S.F.			9,361 S.F.
	ONE PARK V				
	THREE PARK V				
	FOUR PARK V				
	ONE-2 ADDITIONAL UNIT				
	MINIMUM SETBACKS			32.7'	
	FRONT STREET 15' MIN.				
	FRONT STREET 15' MIN.	0'	0'	5.1'	
	BACKYARD 15' MIN.	20'	20'		
	ONE SIDE PROPERTY LINE			56.2'	
	ONE SIDE PROPERTY LINE				
	ONE STREET LINE, 10' COLOR	17'			
	BACKYARD 15' MIN.	22'			
	BACKYARD 15' MIN.				
	MINIMUM LOT AREA	N/A			
	ONE STORY BUILDING	793 S.F.			
	ONE STORY BUILDING	1,000 S.F.			
	TWO LEVEL BUILDING				
	THREE LEVEL BUILDING	1,000 S.F.			
	GROUND FLOOR AREA	N/A		1,000 S.F.	
	FLOOR AREA PER UNIT	500 S.F.		666 S.F.	
	MAX. HEIGHT OVERHANGING	3'			
	MAX. HEIGHT OVERHANGING	3'			
	MAX. BUILDING FOOT OVERHANG	20"		20.4"	
	MAX. BUILDING FOOT OVERHANG				
	MINIMUM FIRST FLOOR ELEVATION	40"			
	MINIMUM FIRST FLOOR ELEVATION				FEET 7'

SURVEY NOTES:

1. This map has been prepared pursuant to the Regulation of Connecticut State Agencies Sections 20-300b-1 through 20-300b-20 and the "Standards for Surveys and Maps in the State of Connecticut" as adopted by the Connecticut Association of Land Surveyors, Inc. on September 26, 1999.

2. Type of survey performed: Zoning Location Survey

3. Boundary determination category: Dependent Resurvey

4. Class of accuracy

Horizontal: A-2
Vertical: Y-2

6. The intent of this map is to depict the position horizontally and where required vertically, between

particular existing or proposed improvements with respect to the applicable municipal or statutory requirements.

6. Map References

a) *Map for James J. Sauty, Fairfield, Conn.*, Prepared by Andrew S. Pennington, Scale 1"=50', Dated April 6, 1937

h) Mean of *Estfield* is same in *EstfieldComp* & *Estfield* but

Bridgeport, Ct". Prepared by W.C. Menzieshouse, Scale: 1"=50'. Dated: June 8, 1917.

7. Per agreement with copyright owner no boundary corners were set by this survey unless noted herein.

All monumentation found is depicted or noted hereon.

8. Zone: BD (Beach District, Residence)

9. Total area: 7,814 S.F. / 0.18 Ac.

10. Owner: Gabriel M. & Gail J. Selig

11. Town of Fairfield Assessors Map #2014/Lot # 790

12. Filed in Volume 1799, Page 213 of the Town Clerk's office.

13. Contours are established from field topography.

14. Vertical Datum is NAVD 1988 and based on the CGS Mon LX 0695.



10. The subject property is in the Coastal Area Management (CAM) and has 1200' wetlands within the boundaries as shown.

16. The subject property is situated in Zone "A1", (Elevation 13.0') which is a "Special Flood Hazard Area"

subject to mutation by the annual variation in the events determined by floods. The 2002 Year Flood Event elevation is 16.25. (See Firm Map 090007 Panel 557 G)

17. This survey does not include the location of any underground improvements or encroachments, subsurface utility lines or buried debris. Nor does it necessarily reflect the existence of voids or dumps.

hazardous materials. The underground items depicted or noted are approximate and are not guaranteed. Notify "CALL BEFORE YOU DIG" 1-800-822-4455 prior to any excavation operations.



- LEGEND**
- = Existing utility pole
 - = Existing light pole
 - = Existing fire hydrant
 - = Existing water valve
 - = Existing gas valve
 - = Existing underground pipe
 - = Existing edge of pavement
 - = Existing bluish-grey concrete curb
 - = Existing wall
 - = Existing catch basin
 - = Existing drainage manhole
 - = Existing sanitary manhole
 - = Existing culvert
 - = Existing spot elevation
 - = Existing iron pin
 - = Existing drill hole
 - = Existing monument

- [illegible]

- | | | |
|-----|---|--|
| 1. | CONST. RESOURCE AT AND ADJACENT TO THE SITE | |
| A. | GENERAL REQUIREMENT | |
| B. | WATER MAINS | |
| C. | SEWER MAINS | |
| D. | ROADS & SIDEWALKS | |
| E. | UTILITIES | |
| F. | TRAIL, WALK AND BIKEWAYS | |
| G. | CONCRETE AND MAINTENANCE WATERCOURSE | |
| H. | CONCRETE AND MAINTENANCE WATERCOURSE | |
| I. | DEVELOPED SHORTPOINT | |
| J. | DEVELOPED SHORTPOINT | |
| K. | DEVELOPED SHORTPOINT | |
| L. | DEVELOPED SHORTPOINT | |
| M. | DEVELOPED SHORTPOINT | |
| N. | DEVELOPED SHORTPOINT | |
| O. | DEVELOPED SHORTPOINT | |
| P. | DEVELOPED SHORTPOINT | |
| Q. | DEVELOPED SHORTPOINT | |
| R. | DEVELOPED SHORTPOINT | |
| S. | DEVELOPED SHORTPOINT | |
| T. | DEVELOPED SHORTPOINT | |
| U. | DEVELOPED SHORTPOINT | |
| V. | DEVELOPED SHORTPOINT | |
| W. | DEVELOPED SHORTPOINT | |
| X. | DEVELOPED SHORTPOINT | |
| Y. | DEVELOPED SHORTPOINT | |
| Z. | DEVELOPED SHORTPOINT | |
| AA. | DEVELOPED SHORTPOINT | |
| AB. | DEVELOPED SHORTPOINT | |
| AC. | DEVELOPED SHORTPOINT | |
| AD. | DEVELOPED SHORTPOINT | |
| AE. | DEVELOPED SHORTPOINT | |
| AF. | DEVELOPED SHORTPOINT | |
| AG. | DEVELOPED SHORTPOINT | |
| AH. | DEVELOPED SHORTPOINT | |
| AI. | DEVELOPED SHORTPOINT | |
| AJ. | DEVELOPED SHORTPOINT | |
| AK. | DEVELOPED SHORTPOINT | |
| AL. | DEVELOPED SHORTPOINT | |
| AM. | DEVELOPED SHORTPOINT | |
| AN. | DEVELOPED SHORTPOINT | |
| AO. | DEVELOPED SHORTPOINT | |
| AP. | DEVELOPED SHORTPOINT | |
| AQ. | DEVELOPED SHORTPOINT | |
| AR. | DEVELOPED SHORTPOINT | |
| AS. | DEVELOPED SHORTPOINT | |
| AT. | DEVELOPED SHORTPOINT | |
| AU. | DEVELOPED SHORTPOINT | |
| AV. | DEVELOPED SHORTPOINT | |
| AW. | DEVELOPED SHORTPOINT | |
| AX. | DEVELOPED SHORTPOINT | |
| AY. | DEVELOPED SHORTPOINT | |
| AZ. | DEVELOPED SHORTPOINT | |
| BA. | DEVELOPED SHORTPOINT | |
| BB. | DEVELOPED SHORTPOINT | |
| BC. | DEVELOPED SHORTPOINT | |
| BD. | DEVELOPED SHORTPOINT | |
| BE. | DEVELOPED SHORTPOINT | |
| BF. | DEVELOPED SHORTPOINT | |
| BG. | DEVELOPED SHORTPOINT | |
| BH. | DEVELOPED SHORTPOINT | |
| BI. | DEVELOPED SHORTPOINT | |
| BJ. | DEVELOPED SHORTPOINT | |
| BK. | DEVELOPED SHORTPOINT | |
| BL. | DEVELOPED SHORTPOINT | |
| BM. | DEVELOPED SHORTPOINT | |
| BN. | DEVELOPED SHORTPOINT | |
| BO. | DEVELOPED SHORTPOINT | |
| BP. | DEVELOPED SHORTPOINT | |
| BQ. | DEVELOPED SHORTPOINT | |
| BR. | DEVELOPED SHORTPOINT | |
| BS. | DEVELOPED SHORTPOINT | |
| BT. | DEVELOPED SHORTPOINT | |
| BU. | DEVELOPED SHORTPOINT | |
| BV. | DEVELOPED SHORTPOINT | |
| BW. | DEVELOPED SHORTPOINT | |
| BX. | DEVELOPED SHORTPOINT | |
| BY. | DEVELOPED SHORTPOINT | |
| BZ. | DEVELOPED SHORTPOINT | |
| CA. | DEVELOPED SHORTPOINT | |
| CB. | DEVELOPED SHORTPOINT | |
| CC. | DEVELOPED SHORTPOINT | |
| CD. | DEVELOPED SHORTPOINT | |
| CE. | DEVELOPED SHORTPOINT | |
| CF. | DEVELOPED SHORTPOINT | |
| CG. | DEVELOPED SHORTPOINT | |
| CH. | DEVELOPED SHORTPOINT | |
| CI. | DEVELOPED SHORTPOINT | |
| CJ. | DEVELOPED SHORTPOINT | |
| CK. | DEVELOPED SHORTPOINT | |
| CL. | DEVELOPED SHORTPOINT | |
| CM. | DEVELOPED SHORTPOINT | |
| CN. | DEVELOPED SHORTPOINT | |
| CO. | DEVELOPED SHORTPOINT | |
| CP. | DEVELOPED SHORTPOINT | |
| CQ. | DEVELOPED SHORTPOINT | |
| CR. | DEVELOPED SHORTPOINT | |
| CS. | DEVELOPED SHORTPOINT | |
| CT. | DEVELOPED SHORTPOINT | |
| CU. | DEVELOPED SHORTPOINT | |
| CV. | DEVELOPED SHORTPOINT | |
| CW. | DEVELOPED SHORTPOINT | |
| CX. | DEVELOPED SHORTPOINT | |
| CY. | DEVELOPED SHORTPOINT | |
| CZ. | DEVELOPED SHORTPOINT | |
| DA. | DEVELOPED SHORTPOINT | |
| DB. | DEVELOPED SHORTPOINT | |
| DC. | DEVELOPED SHORTPOINT | |
| DD. | DEVELOPED SHORTPOINT | |
| DE. | DEVELOPED SHORTPOINT | |
| DF. | DEVELOPED SHORTPOINT | |
| DG. | DEVELOPED SHORTPOINT | |
| DH. | DEVELOPED SHORTPOINT | |
| DI. | DEVELOPED SHORTPOINT | |
| DJ. | DEVELOPED SHORTPOINT | |
| DK. | DEVELOPED SHORTPOINT | |
| DL. | DEVELOPED SHORTPOINT | |
| DM. | DEVELOPED SHORTPOINT | |
| DN. | DEVELOPED SHORTPOINT | |
| DO. | DEVELOPED SHORTPOINT | |
| DP. | DEVELOPED SHORTPOINT | |
| DQ. | DEVELOPED SHORTPOINT | |
| DR. | DEVELOPED SHORTPOINT | |
| DS. | DEVELOPED SHORTPOINT | |
| DT. | DEVELOPED SHORTPOINT | |
| DU. | DEVELOPED SHORTPOINT | |
| DV. | DEVELOPED SHORTPOINT | |
| DW. | DEVELOPED SHORTPOINT | |
| DX. | DEVELOPED SHORTPOINT | |
| DY. | DEVELOPED SHORTPOINT | |
| DZ. | DEVELOPED SHORTPOINT | |
| EA. | DEVELOPED SHORTPOINT | |
| EB. | DEVELOPED SHORTPOINT | |
| EC. | DEVELOPED SHORTPOINT | |
| ED. | DEVELOPED SHORTPOINT | |
| EE. | DEVELOPED SHORTPOINT | |
| EF. | | |

- HOUSE
- N/F
MOLLEY MALONEY CIARDI
&
CARLO B. CIARDI
VOLUME 1900, PAGE 192
- Ex. Pipe

-
- Site plan of the existing garage building. The building is a rectangular structure with a dashed line indicating the 'EXISTING GARAGE' footprint. The plan shows the building's orientation relative to the surrounding streets and property lines. Key features include:
 - Building Dimensions:** The building is 20' wide and 20' deep.
 - Orientation:** The building is oriented with its long side parallel to the 'EXISTING GARAGE' line.
 - Surrounding Streets:** The building is located on a street corner. The street to the left is labeled 'EXISTING GARAGE' and the street to the right is labeled 'EXISTING GARAGE'.
 - Property Lines:** The property lines are shown with dashed lines and dimensions: 40.00' on the left, 40.25' on the right, and 40.25' on the bottom.
 - Other Features:** A 'GARAGE' label is present near the building. A 'GARAGE' label is also present near the bottom right corner.

- [illegible]

2. Field in Volume 175B, Page 2 of 3 of the Town Clerk's Office.

